

(1) Publication numb r: 0 461 274 B1

12

## **EUROPEAN PATENT SPECIFICATION**

(45) Date of publication of patent specification: 15.06.94 Bulletin 94/24

(51) Int. Cl.5: C07C 68/06

(21) Application number: 91901641.0

(22) Date of filing: 28.12.90

86 International application number: PCT/JP90/01734

87 International publication number: WO 91/09832 11.07.91 Gazette 91/15

(A) PROCESS FOR CONTINUOUSLY PRODUCING AROMATIC CARBONATE.

③ Priority: 28.12.89 JP 338179/89 28.12.89 JP 338180/89 21.02.90 JP 38436/90

- (43) Date of publication of application : 18.12.91 Bulletin 91/51
- (45) Publication of the grant of the patent: 15.06.94 Bulletin 94/24
- Designated Contracting States :
   AT BE CH DE ES FR GB IT LI LU NL SE
- (56) References cited:
  JP-A-56 025 138
  JP-A-58 185 536
  JP-A-61 291 545
  US-A- 4 182 726
  US-A- 4 252 737
  Mikitenko, P., "La distillation réactive: principe, applications et perspectives" in Pétrole et Techniques, No 329 (1986), pp. 34-38.

(3) Proprietor : Asahi Kasei Kogyo Kabushiki Kalsha 2-6, Dojimahama 1-chome Kita-ku Osaka-shi Osaka 530 (JP)

72 Inventor: FUKUOKA, Shinsuke
359-11, Yoshioka
Kurashiki-shi
Okayama-ken 710 (JP)
Inventor: TOJO, Masahiro 2-307, Asahi Kasei
Apartment
1005-1, Higashi-Tomii
Kurashiki-shi
Okayama-ken 710 (JP)
Inventor: KAWAMURA, Mamoru
2-443-34, Amanuma-cho
Omiya-shi
Saltama-ken 330 (JP)

(4) Representative : Strehl Schübel-Hopf Groening & Partner Maximilianstrasse 54 D-80538 München (DE)

Note: Within nin months from the publication of the month of the grant of the Europe and patent, any person may give notice to the European Patent Office of opposition to the Europe and patent of the European patent. Notice of physician shall be filled in a written reason of statement. It shall not be deem of the have been filled until the opposition fee has been paid (Art. 99(1) European patent convention).

### D s ription

5

10

20

25

30

45

Th present invention relates to a process for continuously producing an aromatic carbonate. More particularly, the present invention is concerned with a process comprising transest rifying a starting material selected from the group consisting of a dialkyl carbonate represented by

an alkyl aryl carbonate represented by

and a mixture thereof with a reactant selected from the group consisting of an aromatic hydroxy compound represented by Ar¹OH, an alkyl aryl carbonate represented by

and a mixture thereof, to thereby produce an aromatic carbonate or aromatic carbonate mixture corresponding to the starting material and the reactant and represented by

wherein R and Ar are, respectively, selected from R¹, R² and R³ and selected from Ar¹, Ar² and Ar³ in correspondence to the starting material and the reactant, wherein the starting material and the reactant are continuously fed to a continuous multi-stage distillation column to effect a transesterification reaction therebetween in the presence of a catalyst in the distillation column, while continuously withdrawing the aromatic carbonate or aromatic carbonate mixture produced as a high boiling point product in a liquid form from a lower portion of the distillation column and continuously withdrawing a by-product produced as a low boiling point product in a gaseous form from an upper portion of the distillation column by distillation, thereby enabling the aromatic carbonate or aromatic carbonate mixture to be produced continuously with high efficiency.

## **Background Art**

An aromatic carbonate is useful as a raw material for the production of an aromatic polycarbonate (whose utility as engineering plastics has been increasing in recent years) without using poisonous phosgene, or as a raw material for the production of various isocyanates without using poisonous phosgene. With respect to the method for the production of an aromatic carbonate, a method for producing an aromatic carbonate or an aromatic carbonate mixture, is known, in which a dialkyl carbonate, an alkyl aryl carbonate or a mixture thereof is used as a starting material and an aromatic hydroxy compound, an alkyl aryl carbonate or a mixture thereof is used as a reactant, and in which a transesterification reaction is performed between the starting material and the reactant.

How v r, sinc this type of transest rification is a r v rsible reaction in which, moreov r, not only is the equilibrium biased toward the original system but th reaction rate is also low, the production of an aromatic carbonate by the above-mentioned method on an industrial scale is accompanied with great difficulties.

To improve the above-mentioned method, several proposals have been made, most of which r late to the development of a catalyst for increasing the reaction rate. As a catalyst for use in the method for producing

an alkyl aryl carbonate, a diaryl carbonate or a mixture thereof by r acting a dialkyl carbonate with an aromatic hydroxy compound, there have been propos divarious catalysts, which include for exampling a Lewis acid, such as a transition m tal halide, or compounds capable of forming a Lewis acid, [Japan se Patent Application Laid-Open Specification No. 51-105032, Japanese Pat nt Application Laid-Open Specification No. 56-123948 and Japanese Patent Application Laid-Open Specification No. 56-123949 (corresponding to West German Patent Application Laid-Open Specification No. 2528412, British Patent No. 1499530 and U.S. Patent No. 4,182,726)], a tin compound, such as an organotin alkoxide and an organotin oxide [Japanese Patent Application Laid-Open Specification No. 54-48733 (corresponding to West German Patent Application Laid-Open Specification No. 2736062), Japanese Patent Application Laid-Open Specification No. 54-63023, Japanese Patent Application Laid-Open Specification No. 60-169444 (corresponding to U.S. Patent No. 4,554,110), Japanese Patent Application Laid-Open Specification No. 60-169445 (corresponding to U.S. Patent No. 4,552,704), Japanese Patent Application Laid-Open Specification No. 62-277345, and Japanese Patent Application Laid-Open Specification No. 1-265063], salts and alkoxides of an alkali metal or an alkaline earth metal (Japanese Patent Application Laid-Open Specification No. 56-25138), lead compounds (Japanese Patent Application Laid-Open Specification No. 57-176932), complexes of a metal, such as copper, iron and zirconium (Japanese Patent Application Laid-Open Specification No. 57-183745), titanic acid esters [Japanese Patent Application Laid-Open Specification No. 58-185536 (corresponding to U.S. Patent No. 4,410,464)], a mixture of a Lewis acid and protonic acid [Japanese Patent Application Laid-Open Specification No. 60-173016 (corresponding to U.S. Patent No. 4,609,501)], compounds of Sc, Mo, Mn, Bi, Te or the like (Japanese Patent Application Laid-Open Specification No. 1-265064), and ferric acetate (Japanese Patent Application Laid-Open Specification No. 61-172852).

As a catalyst for use in the method for producing a diaryl carbonate by performing disproportionation by means of a same-species intermolecular transesterification of an alkyl aryl carbonate into a diaryl carbonate and a dialkyl carbonate, there have been proposed various catalysts, which include for example, a Lewis acid and a transition metal compound which is capable of forming a Lewis acid [Japanese Patent Application Laid-Open Specification No. 51-75044 (corresponding to West German Patent Application Laid-Open Specification No. 2552907 and U.S. Patent No. 4,045,464)], a polymeric tin compound [Japanese Patent Application Laid-Open Specification No. 60-169444 (corresponding to U.S. Patent No. 4,554,110)], a compound represented by the formula R-X(=0)OH (wherein X is selected from Sn and Ti, and R is selected from monovalent hydrocarbon residues) [Japanese Patent Application Laid-Open Specification No. 60-169445 (corresponding to U.S. Patent No. 4,552,704)], a mixture of a Lewis acid and protonic acid [Japanese Patent Application Laid-Open Specification No. 60-173016 (corresponding to U.S. Patent No. 4,609,501)], a lead catalyst (Japanese Patent Application Laid-Open Specification No. 1-265062), a titanium or zirconium compound (Japanese Patent Application Laid-Open Specification No. 1-265063), and a compound of Sc, Mo, Mn, Bi, Te or the like (Japanese Patent Application Laid-Open Specification No. 1-265064).

25

30

40

50

55

However, the effective improvement of reaction rate cannot be attained by the methods using the abovementioned various catalysts, and therefore, it has been impossible to produce an aromatic carbonate at high selectivity and in high yield by a short-time reaction.

Another attempt for improving the yield of aromatic carbonates in these reactions consists in biasing the equilibrium toward the product system as much as possible. In the case of producing an aromatic carbonate from a dialkyl carbonate and an aromatic hydroxy compound, there have been proposed for example, a method in which by-produced methanol is distilled off together with an azeotrope forming agent by azeotropic distillation in the reaction of a dimethyl carbonate with phenol [Japanese Patent Application Laid-Open Specification No. 54-48732 (corresponding to West German Patent Application Laid-Open Specification No. 2736063) and Japanese Patent Application Laid-Open Specification No. 61-291545] and a method in which by-produced methanol is removed by adsorbing the same onto a molecular sieve [Japanese Patent Application Laid-Open Specification No. 58-185536 (corresponding to U.S. Patent No. 4,410,464)].

However, in the method described in Japanese Patent Application Laid-Open Specification No. 54-48732, a complicated step is required to separate and collect a large quantity of heptane used as an azeotrope forming agent from an azeotrope. In addition, in this method as well, the yield of an aromatic carbonate is as small as 3.5 % relative to the phenol used even after the reaction for a period as long as 45 hours.

Further, in the method describ d in Japanese Patent Application Laid-Op n Specification No. 58-185536, not only is a large quantity of molecular si ve as much as 8-10 g per g of th m thanol by-produced necessary, but also a complicat d step is r quired for desorbing th m thanol adsorb d on the molecular sieve.

Th ref re, it is difficult to carry out these methods on a commercial scal .

Furthermore, as a m thod for performing the intended reaction, which is pref rr d among the methods of the abov -d scrib d proposals, it is known to employ an apparatus comprising a reactor provided on th

top thereof with columns having distillation function or fractional distillation function in ord r to separate and distill off alcohols (by-produc d in the cours of the reaction) from a mixture of the starting material, the product and the solvent co-present the rewith [Japanese Patent Application Laid-Open Specification No. 56-123948 (corresponding to U.S. Patent No. 4,182,726), Japanese Patent Application Laid-Open Specification No. 60-169444 (corresponding to U.S. Patent No. 4,554,110), Japanese Patent Application Laid-Open Specification No. 60-169445 (corresponding to U.S. Patent No. 4,552,704), Japanese Patent Application Laid-Open Specification No. 60-173016 (corresponding to U.S. Patent No. 4,609,501), Japanese Patent Application Laid-Open Specification No. 61-172852, Japanese Patent Application Laid-Open Specification No. 62-277345].

However, in all of the above-mentioned methods, the reaction proceeds only in the reactor in which a catalyst is present. The distillation column provided at the top of the reactor is used only to separate the alcohols (produced in the reactor) from the other components present in the reactor. This is apparent from the detailed description of Japanese Patent Application Laid-Open Specification No. 61-291545. In the Laid-Open specification, for example, there is a description "in such a reaction, generally, a reaction distillation method is employed, in which using a reaction-distillation apparatus in which a reactor is provided with a distillation column, methanol having a boiling point lower than that of the desired carbonate as formed is distilled off from the top of the column while performing the desired reaction in the reactor disposed at the bottom of the column" (page 1, right hand column, lines 12-17 of the Laid-Open specification).

That is, the reaction distillation method in these conventional methods is performed by the use of an apparatus in which a reacting part and a distilling part separately exist. In the part of the distillation column, only distillation is performed but no reaction is conducted. Thus, in these conventional methods, a reaction is performed in a liquid phase in the reactor, but the equilibrium of the reaction is biased toward the product system only by the withdrawal of the low boiling point alcohols by-produced from the liquid phase to a gas phase through a gas-liquid interface to thereby proceed the reaction. However, the reactor used in these methods is of a vessel type, so that the gas-liquid interfacial area is as small as being approximately equal to the cross section area of the reactor, inevitably causing the reaction to be extremely slow, as known in the art. For example, in working examples of Japanese Patent Application Laid-Open Specification Nos. 61-291545, 54-48732 and 54-48733, it takes a reaction time as long as 8-45 hours for a batch system. In the method in which such a prolonged period of time is taken, not only the side-reactions of a starting material or an intermediate product but also the side-reactions of the aromatic carbonates produced are likely to occur to thereby cause a lowering in selectivity. Furthermore, in these reaction methods which take such a prolonged period of time, the productivity is poor, and hence, it is difficult to perform these methods on a commercial scale.

Moreover, with respect to the method known as reaction distillation using an apparatus in which a reacting part and a distilling part are separately disposed, Japanese Patent Application Laid-Open Specification No. 61-291545 has a description to the following effect: "although the reaction distillation operation can be conducted in a batch-wise manner or in a continuous manner, the batch-wise operation is preferred for example, when a dimethyl carbonate is subjected to transesterification with phenol, since the continuous operation requires large-size facilities due to a low reaction rate" (page 3, left hand lower column, lines 4-9). In fact, in all of the working examples of the various publications described above, there is employed either a method in which both of a dialkyl carbonate and an aromatic hydroxy compound as reaction agents are charged together with a catalyst into a reactor from the beginning to effect a reaction, or a method in which only one of the reaction agents (generally, an aromatic hydroxy compound which is a high boiling point compound) is first charged together with a catalyst into a reactor, followed by a reaction while feeding the other reaction agent. Both of the methods are of a batch system. Therefore, up to now, there has been no publication disclosing a continuous reaction method in which both reaction agents are continuously fed while continuously withdrawing products.

## 50 Disclosure of the Invention

20

35

In the above-described situation, the present inventors have made extensive and intensive studies to develop a process free of the drawbacks of the various hitherto proposed processes as mentioned above, which process realizes the continuous production of an aromatic carbonate at a high reaction rate and with a high selectivity. As a result, it has surprisingly be notioned that an aromatic carbonate or an aromatic carbonate mixtur can be continuously produced efficiently at a high reaction rate and with a high selectivity by continuously feeding a starting material and a reactant to a continuous multi-stage distillation column to a ffect a transesterification reaction the rebetween in the presence of a catalyst in the distillation column, while continuously withdrawing the product dearomatic carbonate or aromatic carbonate mixture as a high boiling point product

in a liquid form from a lower portion of the distillation column and continuously withdrawing the by-product as a low boiling point product in a gaseous form from an upper portion of the distillation column by distillation. Further, it has been not found that the desired are matic carbonate or aromatic carbonate mixture can be continuously produced more efficiently by employing a plurality of continuous multi-stage distillation columns in combination so as to effect a skillful recycling of high boiling point products and/or low boiling point products.

The present invention has been made on the basis of these findings.

Accordingly, it is an object of the present invention to provide a novel process for continuously producing an aromatic carbonate efficiently at a high reaction rate and with a high selectivity by using a continuous multi-stage distillation column as a reaction column.

It is another object of the present invention to provide a process in which the desired aromatic carbonate is produced more efficiently by the use of a plurality of continuous multi-stage distillation columns.

Essentially, according to the present invention, there is provided a process for producing an aromatic carbonate which comprises transesterifying a starting material selected from the group consisting of a dialkyl carbonate represented by

20

25

10

15

an alkyl aryl carbonate represented by

and a mixture thereof with a reactant selected from the group consisting of an aromatic hydroxy compound represented by Ar¹OH, an alkyl aryl carbonate represented by

35

40

45

50

30

and a mixture thereof, wherein each of R¹, R² and R³ independently represents an alkyl group having 1 to 10 carbon atoms, an alicyclic group having 3 to 10 carbon atoms or an aralkyl group having 6 to 10 carbon atoms and each of Ar¹, Ar² and Ar³ independently represents an aromatic group having 5 to 30 carbon atoms, to thereby produce an aromatic carbonate or aromatic carbonate mixture corresponding to the starting material and the reactant and represented by

and/or

wher in R and Ar are, respectively, selected from R<sup>1</sup>, R<sup>2</sup> and R<sup>3</sup> and selected from Ar<sup>1</sup>, Ar<sup>2</sup> and Ar<sup>3</sup> in corresponding not the starting material and the reactant and produce an aliphatic alcohol, a dialkyl carbonate or a mixture thereof corresponding to the starting material and the reactant and represented by ROH and/or

wherein R is as defined above, as a by-product, characterized in that the starting material and the reactant are continuously fed to a continuous multi-stage distillation column to effect a liquid phase and/or gas-liquid phase transesterification reaction therebetween in the presence of a catalyst in the distillation column, while continuously withdrawing a high boiling point reaction mixture containing the produced aromatic carbonate or aromatic carbonate mixture in a liquid form from a lower portion of the distillation column and continuously withdrawing a low boiling point reaction mixture containing the by-product in a gaseous form from an upper portion of the distillation column by distillation, thereby enabling the aromatic carbonate or aromatic carbonate mixture to be produced continuously.

The typical reactions which are involved in the process of the present invention are represented by the following formulae:

$$R^{2}OCOAr^{2} + Ar^{1}OH \xrightarrow{\longleftarrow} Ar^{1}OCOAr^{2} + R^{2}OH \qquad ... (2)$$

and

5

10

15

25

40

45

50

$$R^{2}OCOAr^{2} + R^{3}OCOAr^{3} \xrightarrow{<-->} ArOCOAr + ROCOR \dots (4),$$

wherein  $R^1$ ,  $R^2$ ,  $R^3$ ,  $Ar^1$ ,  $Ar^2$  and  $Ar^3$  are as defined above, each of Ar's appearing in formula (4) independently represents  $Ar^2$  or  $Ar^3$ , and each of R's appearing in formula (4) independently represents  $R^2$  or  $R^3$ , and wherein when  $R^2 = R^3$  and  $Ar^2 = Ar^3$  in formula (4), the reaction is a same species-intermolecular transesterification reaction generally known as a disproportionation reaction.

The essential feature of the process of the present invention resides in that the above reactions are performed in the presence of a catalyst in a continuous multi-stage distillation column while separating the low boiling point products formed by the reactions from the reaction system by distillation. The continuous production of an aromatic carbonate at a high selectivity and in a high yield has for the first time become feasible by virtue of this process.

It is really an unexpected finding that the reaction according to the present invention, the equilibrium of which is extremely biased toward the original system [for example, the equilibrium constant of the reaction defined by formula (1) is in the order of 10<sup>-3</sup> to 10<sup>-4</sup>], can be advanced at a high reaction rate by the above process to thereby enable an aromatic carbonate to be continuously produced at a high selectivity and in a high yield.

It is surprising that in the process of the pr sent invention the r action rat is high and th selectivity and yield (or productivity) are markedly improved as compared to thos attain d by th conventional process s. Th xact r ason has not y t been elucidated. However, in light of the results of the practice of the process of the pr sent invention, the following presumptions can b mad.

That is, all of the reactions of th above formulae (1) to (4), which ar involved in the process of the present invention, are reversible reactions, in which the equilibrium is extremely biased toward the original system.

Th refore, in all of the r actions, in order to increase the conv rsion ratio, it is necessary to remove a by-product, which is comprised of low boiling point products formed in the reaction [g nerally, aliphatic alcohols in the reactions of f rmulae (1) and (2) and dialkyl carbonat s in th reactions of formulae (3) and (4)], from the liquid phas in the reaction system as promptly as possible.

However, it has not been possible to increase a reaction rate in the conventional process in which the reaction is conducted using a tank reactor provided in an upper portion thereof with a distillation column as described in the above-mentioned various publications showing the prior art. The reason is that not only is the reaction site limited to only the tank reactor portion where a catalyst is present but the area of a gas-liquid interface necessary for evaporating the low boiling point products formed by the reaction from the liquid phase in the reactor into a gas phase is also small.

10

45

55

By contrast, in the process of the present invention, a catalyst is present throughout a continuous multistage distillation column and, hence, it is possible to advance the reaction in a large region in which an area of a gas-liquid interface is extremely large. In this region, a fed liquid material to be reacted flows down while repeatedly experiencing gas-liquid contact with a vapor ascending from a lower portion and experiencing distillation and reaction. At that time, the low boiling point products are evaporated from the liquid phase into a vapor phase. As a result, each component within the continuous multi-stage distillation column comes to have a biased concentration distribution. For example, when the reactions of formulae (1) and (2) are performed, generally, the concentration of an alkyl aryl carbonate and/or a diaryl carbonate as a high boiling point product in the liquid phase has a distribution such that the concentration gradually increases from the highest stage of the stages in which a catalyst is present toward the lower portion of the column. On the other hand, the concentration of an aliphatic alcohol as a low boiling point product in the liquid phase usually has a distribution such that the concentration gradually decreases from the top portion of the column toward the lower portion of the column. Around the lowermost portion of the column, it is possible to reduce the aliphatic alcohol concentration in the liquid phase to an extremely low level. In the vapor phase, the aliphatic alcohol concentration has a distribution such that it gradually increases from the lower portion of the column toward the upper portion of the column.

When for example, the reactions of formulae (3) and (4) are performed, the concentration of a diaryl carbonate as a high boiling point product in the liquid phase generally has a distribution such that the concentration gradually increases from the highest one of the stages of the column in which a catalyst is present toward the lower portion of the column. On the other hand, the concentration of a dialkyl carbonate as a low boiling point product in the liquid phase usually has a distribution such that the concentration gradually decreases from the upper portion of the column toward the lower portion of the column. Around the lowermost portion of the column, it is possible to reduce the dialkyl carbonate concentration in the liquid phase to an extremely low level. In the vapor phase, the dialkyl carbonate concentration has a distribution such that it gradually increases from the lowermost portion of the column toward the upper portion of the column.

In the process of the present invention, the above reactions proceed as described above in a continuous multi-stage distillation column. It is believed that at an arbitrary position within such a reaction region, the liquid phase of the reaction system is in a condition close to an equilibrium composition as a result of the reaction and the vapor phase has a composition close to a gas-liquid equilibrium condition relative to the liquid phase. Accordingly, when the liquid phase is retained at that position, the reaction is no longer advanced. However, actually, it is possible to further advance the reaction by allowing the liquid phase to flow down so as to effect a gas-liquid contact with a vapor phase in which the concentration of a low boiling point reaction product is lower, thereby further increasing the concentration of an aromatic carbonate as a high boiling point product in the liquid phase.

In the conventional process in which a reaction is performed in a tank reactor provided in the upper portion thereof with a distillation column, a reaction is performed only in the tank reactor, and the distillation column functions only for separating from the low boiling point starting compound vapor a low boiling point product vapor coming from a gas-liquid interface into a gas phase in the tank reactor and allowing the low boiling point starting compound in a liquid form to flow down back to the tank reactor.

Therefore, it is believed that the advantages of the process of the present invention over the conventional process are mainly due to the following points:

- (1) the area of a gas-liquid interface can be extremely large as compared to that provided by the conventional proc ss in which the reaction is performed using a tank reactor, and as a result, the mass transfer of a low boiling point product as a by-product to the vapor phase is facilitated;
- (2) the liquid phas of the reaction system in a continuous multi-stage distillation column flows down while r peatedly experiencing a gas-liquid contact with a vapor ascending from a low r portion and being subjected to reaction and, hence, despite the fact that the process of the present invention is a continuous process, high convirsions of the starting material and their actant can be achieved (in the convintional

proc ss in which the reaction is conducted using a tank reactor, it is difficult to increase the conversion of the starting compound even if the desired aromatic carbonate is continuously withdrawn, and no continuous process has actually been proposed. For increasing the conversion in the conventional process, it is necessary to conduct the reaction in a batchwise manner for a prolenged period of time); and (3) the vapor ascending in a continuous multi-stage distillation column ascends while repeatedly experiencing a gas-liquid contact with a liquid descending in the column and, hence, the thermal energy of the vapor is effectively utilized.

The dialkyl carbonate to be used as a starting material in the present invention is represented by formula

R<sup>1</sup>OCOR<sup>1</sup>,

wherein R¹ represents an alkyl group having 1 to 10 carbon atoms, an alicyclic group having 3 to 10 carbon atoms or an aralkyl group having 6 to 10 carbon atoms. Examples of R¹ include an alkyl group, such as methyl, ethyl, propyl (isomers), allyl, butyl (isomers), butenyl (isomers), pentyl (isomers), hexyl (isomers), heptyl (isomers), octyl (isomers), nonyl (isomers), decyl (isomers) and cyclohexylmethyl; an alicyclic group, such as cyclopropyl, cyclobutyl, cyclopentyl, cyclohexyl and cycloheptyl; and an aralkyl group, such as benzyl, phenethyl (isomers), phenylpropyl (isomers), phenylbutyl (isomers) and methylbenzyl (isomers).

The above-mentioned alkyl group, alicyclic group and aralkyl group may be substituted with a substituent, such as a lower alkyl group, a lower alkoxy group, a cyano group and a halogen atom, as long as the number of carbon atoms of the substituted group does not exceed 10, and may also contain an unsaturated bond.

As a dialkyl carbonate having such R1, there may be mentioned for example, dimethyl carbonate, diethyl carbonate, dipropyl carbonate (isomers), diallyl carbonate, dibutenyl carbonate (isomers), dibutyl carbonate (isomers), dipentyl carbonate (isomers), dihexyl carbonate (isomers), diheptyl carbonate (isomers), dioctyl carbonate (isomers), dicyclopentyl carbonate, dicyclopentyl carbonate, dicyclopentyl carbonate, diphenyl carbonate (isomers), di(phenyl-propyl) carbonate (isomers), di(phenyl-propyl) carbonate (isomers), di(phenyl-propyl) carbonate (isomers), di(methoxymethyl) carbonate, di(methoxyethyl) carbonate (isomers), di(chloroethyl) carbonate (isomers), dicyclopentyl carbonate (isomers), di(chloroethyl) carbonate (isomers), dicyclopentyl carbonate (isomers), di

Of these dialkyl carbonates, a dialkyl carbonate containing as R¹ a lower alkyl group having 4 or less carbon atoms is preferably used. Most preferred is dimethyl carbonate.

The aromatic hydroxy compound to be used as a reactant in the present invention is represented by formula Ar¹OH wherein Ar¹ represents an aromatic group having 5 to 30 carbon atoms, and the type of the compound is not limited as long as the hydroxyl group is directly bonded to the aromatic group. Examples of Ar¹ include a phenyl group and various alkylphenyl groups, such as phenyl, tolyl (isomers), xylyl (isomers), trimethylphenyl (isomers), tetramethylphenyl (isomers), ethylphenyl (isomers), propylphenyl (isomers), butylphenyl (isomers), diethylphenyl (isomers), methylethylphenyl (isomers,), pentylphenyl (isomers), hexylphenyl (isomers) and cyclohexylphenyl (isomers); various alkoxyphenyl groups, such as methoxyphenyl (isomers), ethoxyphenyl (isomers) and butoxyphenyl (isomers); various halogenated phenyl groups, such as fluorophenyl (isomers), chlorophenyl (isomers) and dichlorophenyl (isomers); various substituted phenyl groups represented by the formula:

(O)-- n--(O)--

wherein A represents

a bond, a divalent group, such as -O-, -S-, -CO- and -SO $_2$ -, an alkylene group, a substituted alkylene group of the formula:

55

5

10

15

20

25

30

35

40

45

wherein each of R<sup>4</sup>, R<sup>5</sup>, R<sup>6</sup> and R<sup>7</sup> individually represents a hydrogen atom, a lower alkyl group, a cycloalkyl group, an aryl group or an aralkyl group, which may be substituted with a halogen atom or an alkoxy group),

or a cycloalkylene group of the formula:

5

10

20

30

35

40

50

55

wherein k is an integer of from 3 to 11, and the hydrogen atoms may be substituted with a lower alkyl group, an aryl group, a halogen atom or the like, and

the aromatic group may be substituted with a substituent, such as a lower alkyl group, a lower alkoxy group, an ester group, a hydroxyl group, a nitro group, a halogen and a cyano group;

a naphthyl group and various substituted naphthyl groups, such as naphthyl (isomers), methylnaphthyl (isomers), dimethylnaphthyl (isomers), chloronaphthyl (isomers), methoxynaphthyl (isomers) and cyanonaphthyl (isomers); and various unsubstituted or substituted heteroaromatic groups, such as pyridyl (isomers), cumaryl (isomers), quinolyl (isomers), methylpyridyl (isomers), chloropyridyl (isomers), methylcumaryl (isomers) and methylquinolyl (isomers).

Examples of aromatic hydroxy compounds having these Ar¹ include phenol; various alkyl phenols, such as cresol (isomers), xylenol (isomers), trimethylphenol (isomers), tetramethylphenol (isomers), ethylphenol (isomers), propylphenol (isomers), butylphenol (isomers), diethylphenol (isomers), methylphenol (isomers), methylphenol (isomers), pentylphenol (isomers), hexylphenol (isomers) and cyclohexylphenol (isomers); various alkoxyphenols, such as methoxyphenol (isomers) and ethoxyphenol (isomers); various substituted phenols represented by the formula:

wherein A is as defined above;

naphthol (isomers) and various substituted naphthols; and heteroaromatic hydroxy compounds, such as hydroxypyridine (isomers), hydroxycumarine (isomers) and hydroxyquinoline (isomers). Also usable are an aromatic dihydroxy compound having two hydroxyl groups, such as hydroquinone, resorcinol, catechol, dihydroxynaphthalene, dihydroxyanthracene and a dihydroxy compound obtained by substitution of the above with an alkyl group; and an aromatic dihydroxy compound represented by the formula:

wherein A is as defined above, and the aromatic ring may be substituted with a substituent, such as a lower alkyl group, a lower alkoxy group, an ester group, a nitro group, a cyano group and a halogen atom. Of these aromatic hydroxy compounds, an aromatic monohydroxy compound containing as Ar¹ an aromatic group having 6 to 10 carbon atoms is pref rably us d in the present invintion, and phinol is most preferriced.

The alkyl aryl carbonate to be used as a starting material in the present invention is represented by the formula:

5

10

25

30

40

45

50

55

wherein R<sup>2</sup> may be identical with or different from R<sup>1</sup>, and represents an alkyl group having 1 to 10 carbon atoms, an alicyclic group having 3 to 10 carbon atoms or an aralkyl group having 6 to 10 carbon atoms; and Ar<sup>2</sup> may be identical with or different from Ar<sup>1</sup>, and represents an aromatic group having 5 to 30 carbon atoms. As R<sup>2</sup>, there may be mentioned for example, the same groups as set forth above for R<sup>1</sup>. As Ar<sup>2</sup>, there may be mentioned for example, the same groups as set forth above for Ar<sup>1</sup>.

Representative examples of alkyl aryl carbonate having these R² and Ar² include methyl phenyl carbonate, ethyl phenyl carbonate, propyl phenyl carbonate (isomers), allyl phenyl carbonate, butyl phenyl carbonate (isomers), pentyl phenyl carbonate (isomers), hexyl phenyl carbonate (isomers), heptyl phenyl carbonate (isomers), octyl tolyl carbonate (isomers), nonyl ethylphenyl carbonate (isomers), decyl butylphenyl carbonate (isomers), methyl tolyl carbonate (isomers), methyl tolyl carbonate (isomers), methyl tolyl carbonate (isomers), methyl trimethylphenyl carbonate (isomers), methyl chlorophenyl carbonate (isomers), methyl nitrophenyl carbonate (isomers), methyl methoxyphenyl carbonate (isomers), methyl cumyl carbonate (isomers), methyl pyridyl carbonate (isomers), methyl cumyl carbonate (isomers), methyl pyridyl carbonate (isomers), benzyl xylyl carbonate (isomers), methyl hydroxyphenyl carbonate (isomers), methyl hydroxyphenyl carbonate (isomers), methyl hydroxyphenyl carbonate (isomers), methyl 2-(hydroxyphenyl)propylphenyl carbonate (isomers) and ethyl 2-(hydroxyphenyl)propylphenyl carbonate (isomers). Of these alkyl aryl carbonates, one containing as R² an alkyl group having 1 to 4 carbon atoms and as Ar² an aromatic group having 6 to 10 carbon atoms is preferably used, and methyl phenyl carbonate is most preferred.

The alkyl aryl carbonate to be used as a reactant in the present invention is represented by the formula:

wherein R³ may be identical with or different from R¹ and R², and represents an alkyl groups having 1 to 10 carbon atoms, as alicyclic group having 3 to 10 carbon atoms or an aralkyl group having 6 to 10 carbon atoms; and Ar³ may be identical with or different from Ar¹ and Ar², and represents and aromatic group having 5 to 30 carbon atoms. As R³, there may be mentioned for example, the same groups as set forth above for R¹. As Ar³, there may be mentioned for example, the same groups as set forth above for Ar¹.

As alkyl aryl carbonates having these R³ and Ar³, there may be mentioned for example, those which are set forth above for

$$R^2$$
OCOAr $^2$ .

Of these alkyl aryl carbonates, one containing as R³ an alkyl group having 1 to 4 carbon atoms and as Ar³ an aromatic group having 6 to 10 carbon atoms, and methyl phenyl carbonate is most preferred.

When each of the reactions of formulae (1), (2), (3) and (4) is performed according to the process of the present invention, dialkyl carbonates or alkyl aryl carbonates as starting materials for the reaction can be used individually or in mixture and aromatic hydroxy compounds or alkyl aryl carbonates as reactants for the reaction can be used individually or in mixture.

When R<sup>2</sup>=R<sup>3</sup>=R and Ar<sup>2</sup>=Ar<sup>3</sup>=Ar in the transesterification reaction of formula (4), a diaryl carbonate and a dialkyl carbonate can b obtained by a same species-intermolecular transesterification reaction of a single typ of alkyl aryl carbonate. This is a pr ferr d embodiment of the present invention.

Further, wh n R<sup>1</sup>=R<sup>2</sup>=R<sup>3</sup>=R and Ar<sup>1</sup>=Ar<sup>2</sup>=Ar<sup>3</sup>=Ar in formulae (1) and (4), by combining the reaction of formula (1) with the r action of formula (4), a diaryl carbonate can be obtained from a dialkyl carbonate and an aromatic hydroxy compound through an alkyl aryl carbonate as shown in formula (5) and (6). This is an specially pr ferred embodim nt of the present invention.

Recycling of the dialkyl carbonate by-produced in the reaction of formula (6) as a starting material for the reaction of formula (5) results in the formation of 1 mol. of a diaryl carbonate and 2 mol. of an aliphatic alcohol from 1 mol. of a dialkyl carbonate and 2 mol. of an aromatic hydroxy compound.

When  $R=CH_3$  and  $Ar=C_6H_5$  in the above formulae (5) and (6), diphenyl carbonate, which is an important raw material for polycarbonate and an isocyanate, can be readily obtained from dimethyl carbonate, which is the simplest form of dialkyl carbonate, and phenol. This is especially important.

As a catalyst to be used in the present invention, there may be mentioned for example: (lead compounds)

a lead oxides, such as PbO, PbO<sub>2</sub> and Pb<sub>3</sub>O<sub>4</sub>; lead sulfides, such as PbS and Pb<sub>2</sub>S; lead hydroxides, such as Pb(OH)<sub>2</sub> and Pb<sub>2</sub>O<sub>2</sub>(OH)<sub>2</sub>; plumbites, such as Na<sub>2</sub>PbO<sub>2</sub>, K<sub>2</sub>PbO<sub>2</sub>, NaHPbO<sub>2</sub> and KHPbO<sub>2</sub>; a plumbate, such as Na<sub>2</sub>PbO<sub>3</sub>, Na<sub>2</sub>H<sub>2</sub>PbO<sub>4</sub>, K<sub>2</sub>PbO<sub>3</sub>, K<sub>2</sub>[Pb(OH)<sub>6</sub>], K<sub>4</sub>PbO<sub>4</sub>, Ca<sub>2</sub>PbO<sub>4</sub> and CaPbO<sub>3</sub>; lead carbonates and basic salts thereof, such as PbCO<sub>3</sub> and 2PbCO<sub>3</sub>·Pb(OH)<sub>2</sub>; lead salts of organic acids, and carbonates and basic salts thereof, such as Pb(OCOCH<sub>3</sub>)<sub>2</sub>, Pb(OCOCH<sub>3</sub>)<sub>4</sub> and Pb(OCOCH<sub>3</sub>)<sub>2</sub>·PbO·3H<sub>2</sub>O; organolead compounds, such as Bu<sub>4</sub>Pb, Ph<sub>4</sub>Pb, Bu<sub>3</sub>PbC1, Ph<sub>3</sub>PbBr, Ph<sub>3</sub>Pb (or Ph<sub>6</sub>Pb<sub>2</sub>), Bu<sub>3</sub>PbOH and Ph<sub>3</sub>PbO wherein Bu represents a butyl group and Ph represents a phenyl group; alkoxylead compounds and aryloxylead compounds , such as Pb(OCH<sub>3</sub>)<sub>2</sub>, (CH<sub>3</sub>O)Pb(OPh) and Pb(OPh)<sub>2</sub>; lead alloys, such as Pb-Na, Pb-Ca, Pb-Ba, Pb-Sn and Pb-Sb; lead minerals, such as galena and zincblende; and hydrates of these lead compounds; (copper family metal compounds)

salts or complexes of a copper family metal, such as CuCl, CuCl₂, CuBr, CuBr₂, Cul, Cul₂, Cu(OAc)₂, Cu(acac)₂, copper oleate, Bu₂Cu, (CH₃O)₂Cu, AgNO₃, AgBr, silver picrate, AgC₀H₀ClO₄, Ag(bullvalene)₃NO₃, [AuC≡C-C(CH₃)₃]n and [Cu(C₁H₀)Cl]₄ wherein OAc represents an acetyl group and acac represents an acetylacetone chelate ligand;

(alkali metal complexes)

5

10

15

30

35

55

alkali metal complexes, such as Li(acac) and LiN( $C_4H_9$ )<sub>2</sub> wherein acac is as defined above; (zinc complexes)

zinc complexes, such as Zn(acac)<sub>2</sub> wherein acac is as defined above; (cadmium complexes)

cadmium complexes, such as Cd(acac)<sub>2</sub> wherein acac is as defined above;

(iron family metal compounds)

 $Fe(C_{10}H_8)(CO)_5$ ,  $Fe(CO)_5$ ,  $Fe(C_3H_6)(CO)_3$ ,  $Co(mesitylene)_2(PEt_2Ph)_2$ ,  $CoC_5F_6(CO)_2$ ,  $Ni-\pi-C_5H_8NO$  and ferrocene;

(zirconium complexes)

zirconium complexes, such as Zr(acac)<sub>4</sub> wherein acac is as defined above and zirconocene; (Lewis acids and Lewis acid-forming compounds)

Lewis acids and Lewis acid-forming transition metal compounds, such as AIX<sub>3</sub>, TiX<sub>3</sub>, TiX<sub>4</sub>, VOX<sub>3</sub>, VX<sub>5</sub>, ZnX<sub>2</sub>, FeX<sub>3</sub> and SnX<sub>4</sub> wherein X represents a halogen, an acetoxy group, an alkoxy group or an aryloxy group; (organotin compounds)

organotin compounds, such as  $(CH_3)_3SnOCOCH_3$ ,  $(C_2H_5)_3SnOCOC_6H_5$ ,  $Bu_3SnOCOCH_3$ ,  $Ph_3SnOCOCH_3$ ,  $Bu_2Sn(OCOCH_3)_2$ ,  $Bu_2Sn(OCOC_{11}H_{23})_2$ ,  $Ph_3SnOCH_3$ ,  $(C_2H_5)_3SnOPh$ ,  $Bu_2Sn(OCH_3)_2$ ,  $Bu_2Sn(O$ 

inorganic oxides, such as silica, alumina, titania, silicatitania, zinc oxide, zirconium oxide, gallium oxide zeolite and an oxide of a rare arth; and a material obtain d by modifying the surfac acid site of the abov inorganic oxide by silylation or other m thods.

These catalysts may be either soluble or insoluble in the liquid phase of the reaction system. Further, these catalysts may be used in the form of a mixture with a compound or a carrier which is in in the the reaction or a composite having the catalyst supported on such a compound or a carrier.

Thes catalysts are effective v n when they ar reacted with an organic compound present in the reac-

tion syst m, such as an aliphatic alcohol, an aromatic hydroxy compound, an alkyl aryl carbonate, a diaryl carbonate and a dialkyl carbonat. Alternatively, these catalysts may be heat treated with a feedstock, i.e., a starting material and a reactant, in a corresponding product prior to the use in the process of the present invention.

Of these catalysts, especially preferred are lead compounds, for example, lead oxides, such as PbO, PbO<sub>2</sub> and Pb<sub>3</sub>O<sub>4</sub>, lead hydroxides, such as Pb(OH)<sub>2</sub> and Pb<sub>2</sub>O<sub>2</sub>(OH)<sub>2</sub>, lead carbonates and basic salts thereof, such as PbCO<sub>3</sub> and 2PbCO<sub>3</sub>·Pb(OH)<sub>2</sub>, alkoxylead compounds and aryloxylead compounds, such as Pb(OCH<sub>3</sub>)<sub>2</sub>, (CH<sub>3</sub>O)Pb(OPh) and Pb(OPh)<sub>2</sub>. Further, those which are formed by reacting such a lead compound with an organic compound present in the reaction system and those which are obtained by heat treating, prior to the reaction, such a lead compound with a feedstock, i.e., a starting material and a reactant, or a corresponding product, may preferably be used.

There is no limitation with respect to the continuous multi-stage distillation column to be used in the present invention as long as it is a distillation column having a theoretical number of plates of distillation of two or more and which is capable of continuous distillation. Examples of such continuous multi-stage distillation columns include plate type columns using a tray, such as a bubble-cap tray, a sieve tray, a valve tray and a counterflow tray, and packed type columns packed with various packings, such as a Raschig ring, a Lessing ring, a Pall ring, a Berl saddle, an Intelox saddle, a Dixon packing, a McMahon packing, a Heli pack, a Sulzer packing and Mellapak. Any column which is generally used as a continuous multi-stage distillation column can be utilized. (In the present invention, "the number of stages of a distillation column" means the number of plates with respect to a plate column and the number of theoretical plates with respect to the other types of distillation columns including a packed column.) Further, a mixed type of plate column and packed column comprising both a plate portion and a portion packed with packings, can also be preferably used. When a solid catalyst which is insoluble in the liquid phase in a distillation column is used, a packed column type distillation column in which the solid catalyst is used in substitution for part or all of the packings, is preferably employed.

In the present invention, it is requisite that a catalyst be present in the continuous multi-stage distillation column, and it is preferred that the catalyst be present in at least two plates of the continuous multi-stage distillation column.

The method for allowing a catalyst to be present in the continuous multi-stage distillation column is not limited. For example, when a homogeneous catalyst soluble in the liquid phase in the distillation column is used, the catalyst can be allowed to be present in the reaction system by continuously feeding the catalyst to the distillation column, and when a heterogeneous catalyst (solid catalyst) insoluble in the liquid phase in the distillation column is used, the catalyst can be allowed to be present in the reaction system by disposing the solid catalyst in the distillation column. These methods can be used in combination.

When a homogeneous catalyst is continuously fed to the distillation column, it may be fed to the column simultaneously with the feedstock in the form of a mixture of the catalyst and either one or both of the starting material and the reactant. Alternatively, the homogeneous catalyst may be fed to a plate which is different from the plate where the feedstock is fed. Further, the catalyst can be fed at any position as long as the position is at least one plate above the column bottom. However, since the region where the reaction actually takes place in the distillation column is generally below the position where the catalyst is fed, it is preferred that the catalyst be fed to a region between the column top and the position for feeding the feedstock. When a heterogeneous solid catalyst is used, the catalyst can be packed in a desired quantity in a desired position of the distillation column, as long as the theoretical number of stages for the layer in which the catalyst is present is at least one, preferably at least two. This solid catalyst also serves as a packing for the distillation column.

In a region of the column where no catalyst is present, the distillation column serves only as an ordinary distillation column, for example, functions for concentration of the reaction product.

As described above, the process according to the essential aspect of the present invention is a process for producing an aromatic carbonate which comprises transesterifying a starting material selected from the group consisting of a dialkyl carbonate represented by

an alkyl aryl carbonate repr sented by

10

15

20

25

35

40

45

50

5

10

15

20

25

30

35

40

45

50

55

and a mixture thereof with a reactant selected from the group consisting of an aromatic hydroxy compound represented by Ar¹OH, an alkyl aryl carbonate represented by

and a mixture thereof, wherein each of  $R^1$ ,  $R^2$  and  $R^3$  independently represents an alkyl group having 1 to 10 carbon atoms, an alicyclic group having 3 to 10 carbon atoms or an aralkyl group having 6 to 10 carbon atoms and each of  $Ar^1$ ,  $Ar^2$  and  $Ar^3$  independently represents an aromatic group having 5 to 30 carbon atoms, to thereby produce an aromatic carbonate or aromatic carbonate mixture corresponding to the starting material and the reactant and represented by

wherein R and Ar are, respectively, selected from R¹, R² and R³ and selected from Ar¹, Ar² and Ar³ in correspondence to the starting material and the reactant and produce an aliphatic alcohol, a dialkyl carbonate or a mixture thereof corresponding to the starting material and the reactant and represented by ROH and/or

wherein R is as defined above, as a by-product, characterized in that the starting material and the reactant are continuously fed to a continuous multi-stage distillation column to effect a liquid phase and/or gas-liquid phase transesterification reaction therebetween in the presence of a catalyst in the distillation column, while continuously withdrawing a high boiling point reaction mixture containing the produced aromatic carbonate or aromatic carbonate mixture in a liquid form from a lower portion of the distillation column and continuously withdrawing a low boiling point reaction mixture containing the by-product in a gaseous form from an upper portion of the distillation column by distillation, thereby enabling the aromatic carbonate or aromatic carbonate mixture to be produced continuously. There is no particular restriction with respect to the method for continuously feeding the starting material and the reactant to the continuous multi-stage distillation column, and any feeding method can be used as long as the starting material and the reactant can be contacted with the catalyst in a region of the distillation column which corresponds to at least one plate, preferably at least two plates. For example, the starting material and the reactant can be continuously fed to the continuous multi-stage distillation column from a desired number of feeding pipes onto a desired plate. The starting material and the reactant may be fed either to the same plate of the distillation column or individually to separate plates.

The starting material and the reactant are continuously fed in a liquid form, a gaseous form, or a liquidgas form.

Besides the feeding of the starting material and the reactant to the continuous multi-stage distillation column as decribed above, it is also preferred to additionally feed the starting material and/or the reactant in a gaseous form to the low reportion of the distillation column intermittently or continuously.

Also preferabl is a method wherein the higher boiling point component of the f dstock composed of th starting material and th reactant is continuously fed in a liquid form or a liquid-gas mixture form to a plat at a level high r than the plate where the catalyst is present, while the lower boiling point component of the fe dstock is continuously fed in a gas ous form to the lower portion of the distillation column. In this case, some of the lower boiling point component of the feedstock may be contain d in the higher boiling point component

of the f dstock fed to the upper portion of the column.

30

The f dstock may contain products, i.e., an aliphatic alcohol and an alkyl aryl carbonate or a diaryl carbonat (in the case of the reaction of formula 1 or 2), or a dialkyl carbonat and an alkyl aryl carbonate (in the case of the reaction of formula 3 or 4). However, too high a concentration of these products is undesirable, because the reactions of formulae 1 to 4 involved in the process of the present invention are reversible and, therefore, too high a concentration of these products causes the rate of conversion of the feedstock to be lowered.

The ratio of the reactant to the starting material to be fed to the continuous multi-stage distillation column may vary depending on the type and quantity of the catalyst and the reaction conditions, but, in general, the molar ratio of the reactant to the starting material is preferably in the range of from 0.01 to 1000.

In the present invention, the starting material is reacted with the reactant in the presence of a catalyst within the continuous multi-stage distillation column, to thereby produce an aromatic carbonate corresponding to the starting material and the reactant as a desired product and produce an aliphatic alcohol [in the case of the reactions of formulae (1) and (2)] or a dialkyl carbonate [in the case of the reactions of formulae (3) and (4)] corresponding to the starting material and the reactant as a by-product. The desired product or the by-product, whichever is lower in boiling point, i.e., a low boiling point reaction product is continuously withdrawn in a gaseous form from the distillation column. In the reaction involved in the process of the present invention, the by-produced aliphatic alcohol or dialkyl carbonate is generally lower in boiling point than the desired aromatic carbonate and, hence, the by-product is continuously withdrawn in a gaseous form from the distillation column. In this case, the withdrawn gaseous product may be either the low boiling point by-product alone or a mixture of the by-product and the starting material and/or reactant. Further, the withdrawn gaseous product may contain an aromatic carbonate, which is a high boiling point product, in a small amount.

The outlet for withdrawing the gaseous material containing a low boiling point by-product from the continuous multi-stage distillation column can be provided at an appropriate position in the column except the column bottom. The concentration of the low boiling point by-product in the vapor phase, in general, increases in accordance with the distance from the column bottom. Therefore, the outlet for the gaseous material is preferably provided at a position above both of the positions from which the starting material and the reactant as feedstocks are fed, i.e., between the feeding positions and the column top or in the column top, and it is particularly preferred to provide the outlet in the column top.

The gaseous component withdrawn in this way is liquidfied by cooling or the like, and a portion of the resultant liquid may be returned to the upper portion of the distillation column to thereby effect the so-called reflux operation. When the reflux ratio is increased by conducting this reflux operation, the distillation efficiency of a low boiling point by-product into a vapor phase is increased, thereby advantageously increasing the concentration of the low boiling point by-product in the withdrawn gaseous component. However, too much an increase in the reflux ratio disadvantageously leads to an increase in the thermal energy required. Thus, the reflux ratio is generally chosen in the range of from 0 to 20, preferably from 0 to 10.

An aromatic carbonate which is the desired product produced by the method of the present invention is continuously withdrawn form as a high boiling point product in a liquid from the lower portion of the continuous multi-stage distillation column. In this instance, the withdrawn liquid material may be either an aromatic carbonate alone or a mixture of an aromatic carbonate and the starting material and/or reactant, and may contain a little amount of a low boiling point product. When a high boiling point catalyst soluble in a liquid phase is used, the catalyst is contained in this withdrawn liquid material. The outlet for withdrawing a liquid material containing the desired product, i.e., an aromatic carbonate, from the continuous multi-stage distillation column, is provided in a lower portion of the column. A portion of the liquid material withdrawn in this way may be recycled to a lower portion of the distillation column in a gaseous form or a gas-liquid mixture form by heating by means of a reboiler.

The amount of the catalyst to be used in the present invention varies depending on the type thereof, the type of the continuous multi-stage distillation column, the types and proportions of the starting material and the reactant, the reaction conditions, such as reaction temperature and reaction pressure, and the like. When the catalyst is continuously fed to the reaction zone of the continuous multi-stage distillation column, the catalyst is generally used in an amount of from 0.0001 to 50 % by weight, based on the total weight of the starting material and the reactant constituting the feedstock. When a solid catalyst disposed in the continuous multi-stage distillation column is employed, the catalyst is pref rably us d in an amount of from 0.01 t 75 % by volume, based on the volume of an empty distillation column.

In the present invention the reaction tak splace within the continuous multi-stage distillation column in which the catalyst is present, and, therefore, the quantity of the reaction product generally depends on the amount of the hold-up liquid in the distillation column. That is, when the height and the diameter of a distillation column are not changed, a greater hold-up capacity is preferred because the greater the hold-up capacity,

the long rth residence time of the liquid phase, that is, the time during which the reaction is effected. However, whin the amount of the hold-up liquid is too large, this risid not time becomes too long, so that side reactions and flooding are likely to occur. Accordingly, in the present invention the amount of the hold-up liquid of the distillation column varies dipending on the distillation conditions and the type of the distillation column. Generally, however, the amount of the hold-up liquid is in the range of from 0.005 to 0.75 in terms of the volume ratio of the hold-up liquid to the empty continuous multi-stage distillation column.

In the present invention, the average residence time of the liquid phase in the continuous multi-stage distillation column depends on the reaction conditions, the type and inner structure (for example, the types of the plate and packing) of the continuous multi-stage distillation column, but is generally in the range of from 0.001 to 50 hr, preferably from 0.01 to 10 hr, more preferably from 0.05 to 2 hr.

10

20

25

30

The reaction temperature means the temperature of the inside of the continuous multi-stage distillation column. The reaction temperature varies depending on the types of the starting material and the reactant, but is generally chosen in the range of from 50 to 350 °C, preferably from 100 to 280 °C. The reaction pressure varies depending on the types of the starting material and reactant and the reaction temperature, and it may be any of a reduced pressure, an atmospheric pressure and a superatmospheric pressure. The pressure is generally in the range of from 13,3 Pa (0.1 mmHg) to 200 kg/cm².

It is not always necessary to use a solvent in the present invention. For the purpose of facilitating the reaction operation, an appropriate inert solvent, such as ethers, aliphatic hydrocarbons, aromatic hydrocarbons, halogenated aliphatic hydrocarbons and halogenated aromatic hydrocarbons, may be used as a reaction solvent.

An inert gas, such as nitrogen, helium, argon and the like, may be present in the reaction system as a material inert to the reaction. Further, the above-mentioned inert gas and a reaction-inert low boiling point organic compound may be introduced in a gaseous form to the lower portion of the continuous multi-stage distillation column for the purpose of accelerating the distilling-off of a produced low boiling point by-product.

In order to explain the process of the present invention illustratively, a mode of the process using a single continuous multi-stage distillation column is described below. The present invention, however, is not restricted to the following mode of the process.

For example, as shown in Fig. 1, both a mixed feedstock comprised of a starting material and a reactant and a catalyst are continuously fed from feeding pipe 2 through preheater 5 to continuous multi-stage distillation column 1 provided with reboiler 10 and condenser 13, and the column bottom liquid is heated by reboiler 10, thereby effecting reaction and distillation. A liquid component containing an aromatic carbonate which is a high boiling point product produced in the presence of the catalyst within the continuous multi-stage distillation column, is continuously withdrawn from the lower portion of the column as column bottom liquid 19. A gaseous component containing a low boiling point product which is a by-product is continuously withdrawn as column top gas 12, and condensed by condenser 13, and then continuously withdrawn as column top liquid 16. A portion of the column top liquid may be refluxed to the upper portion of the continuous multi-stage distillation column from 15.

As shown in Fig. 2, both a mixed feedstock comprised of a starting material and a reactant and a catalyst are continuously fed from feeding pipe 2 through preheater 5 to continuous multi-stage distillation column 1, while the starting material or the reactant, whichever is lower in boiling point, is introduced from feeding pipe 8', evaporized by evaporator 10' and then continuously fed to the lower portion of continuous multi-stage distillation column 1, thereby effecting reaction and distillation. A liquid component containing an aromatic carbonate which is a high boiling point product produced in the presence of a catalyst within the continuous multi-stage distillation column, is continuously withdrawn as column bottom liquid 19 from the lower portion of the column. A gaseous component containing a low boiling point product which is a reaction by-product is continuously withdrawn as column top gas 12 and condensed by condenser 13, and then continuously withdrawn as column top liquid 16.

In the process of the present invention, a diaryl carbonate can be continuously produced with improved efficiency from a dialkyl carbonate and an aromatic hydroxy compound by the use of a plurality of, particularly two, continuous multi-stage distillation columns.

That is, in the second aspect of the present invention, there is provided a process according to the abovementioned essential aspect of the present invention, wherein the continuous multi-stage distillation column is used as a first continuous multi-stage distillation column and has a second continuous multi-stage distillation column conn cted th reto and wherein the starting material and the reactant which are continuously fed to the first continuous multi-stage distillation column are, respectively, a dialkyl carbonate represented by

and an aromatic hydroxy compound represented by Ar¹OH, the aromatic carbonate or aromatic carbonate mixture contained in the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column is an alkyl aryl carbonate represented by

in which R¹and Ar¹ are as defined above, and the by-product contained in the produced low boiling point reaction mixture continuously withdrawn from the upper portion of the first distillation column is an aliphatic alcohol represented by R¹OH, and which process further comprises continuously feeding the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column and containing the alkyl aryl carbonate represented by

in which R1 and Ar1 are as defined above, and an alkyl aryl carbonate reactant represented by

in which R³ is the same as or different from R¹ and Ar³ is the same as or different from Ar¹ with the proviso that R³ and Ar³ are, respectively, not simultaneously the same as R¹ and Ar¹, to the second continuous multistage distillation column to effect a liquid phase and/or gas-liquid phase transesterification reaction therebetween in the presence of a catalyst in the second distillation column, thereby producing a high boiling point reaction mixture containing a diaryl carbonate or diaryl carbonate mixture represented by

$$Ar^{1}OCOAr^{1}$$
,  $Ar^{1}OCOAr^{3}$  and/or  $Ar^{3}OCOAr^{3}$ ,

45 in which Ar¹ and Ar³ are as defined above, and a low boiling point reaction mixture containing a dialkyl carbonate by-product represented by

and/or

5

10

15

20

25

30

35

40

50

in which R¹ and R³ ar as defined above, wherein the produced high boiling point reaction mixture is continuously withdrawn in a liquid form from a low r portion of the second distillation column and the low boiling point r action mixture is continuously withdrawn in a gaseous form from an upper portion of the second distillation column by distillation.

In the above-mentioned method according to the second aspect of the present invention, it is preferred that the catalyst be a catalyst which is soluble in the liquid phase, being present in a state dissolved in the liquid phase within at least one of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column, and/or that the catalyst be a solid catalyst which is substantially insoluble in the liquid phase, being disposed, in a state undissolved in the liquid phase, within at least one of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column.

When R³ is the same as R¹ and Ar³ is different from Ar¹, it is desirable to recycle the low boiling point reaction mixture withdrawn from the upper portion of the second continuous multi-stage distillation column and containing a dialkyl carbonate represented by

R<sup>1</sup>OCOR<sup>3</sup>

to the first continuous multi-stage distillation column.

5

10

15

20

30

35

40

50

55

In the third aspect of the present invention, there is provided a process according to the above-mentioned essential aspect of the present invention, wherein the continuous multi-stage distillation column is used as a first continuous multi-stage distillation column and has a second continuous multi-stage distillation column connected thereto and wherein the starting material and the reactant which are continuously fed to the first continuous multi-stage distillation column are, respectively, a dialkyl carbonate represented by

R<sup>1</sup>OCOR<sup>1</sup>

and an aromatic hydroxy compound represented by Ar¹OH, the aromatic carbonate or aromatic carbonate mixture contained in the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column is an alkyl aryl carbonate represented by

R<sup>1</sup>OCOAr<sup>1</sup>

in which R¹ and Ar¹ are as defined above, and the by-product contained in the produced low boiling point reaction mixture continuously withdrawn from the upper portion of the first distillation column is an aliphatic alcohol represented by R¹OH, and which process further comprises continuously feeding the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column and containing the alkyl aryl carbonate represented by

R<sup>1</sup>OCOAr<sup>1</sup>,

to the second continuous multi-stage distillation column to effect a liquid phase and/or gas-liquid phase, same sp cies-int rmolecular transesterification reaction between molecules of the alkyl aryl carben nate in the presence of a catalyst in the second distillation column, the reby producing a high boiling point reaction mixtur containing a diaryl carbonate represented by

5

in which Ar1 is as defined above, and a low boiling point reaction mixture containing a dialkyl carbonate byproduct represented by

10

wherein the produced high boiling point reaction mixture is continuously withdrawn in a liquid form from a lower portion of the second continuous multi-stage distillation column and the low boiling point reaction mixture is continuously withdrawn by distillation in a gaseous form from an upper portion of the second continuous multi-stage distillation column.

In the above-mentioned third aspect as well, it is preferred to recycle the low boiling point reaction mixture withdrawn from the upper portion of the second continuous multi-stage distillation column and containing the dialkyl carbonate represented by

R<sup>1</sup>OCOR<sup>1</sup>

25

30

35

to the first continuous multi-stage distillation column.

In the method according to the above-mentioned third aspect, it is preferred that the catalyst be a catalyst which is soluble in the liquid phase, and is present in a state dissolved in the liquid phase within at least one of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column, and/or that the catalyst be a solid catalyst which is substantially insoluble in the liquid phase, and is disposed, in a state undissolved in the liquid phase, within at least one of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column.

When the catalyst is a catalyst which is soluble in the liquid phase, it is preferred that the catalyst be present in a state dissolved in the liquid phase within each of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column, wherein the respective catalysts used in the first and second distillation columns are the same or different.

When a catalyst which is soluble in the liquid phase of such a reaction system is used, it is desirable to add a catalyst separation step so as to enable the catalyst to be recycled. That is, when part or all of the catalyst used in the first continuous multi-stage distillation column is present in a state dissolved in the liquid phase, it is preferred that, in feeding to the second continuous multi-stage distillation column the high boiling point reaction mixture withdrawn in liquid form from the lower portion of the first distillation column, the withdrawn high boiling point reaction mixture in liquid form be introduced to a first evaporator to effect a separation of the reaction mixture into an evaporated component containing the alkyl aryl carbonate represented by

50

55

and a residual liquid having the catalyst dissolved therein, and that part or all of evaporated component be continuously fed to the second continuous multi-stage distillation column, while recycling part or all of the residual liquid containing the dissolved catalyst to the first continuous multi-stage distillation column.

The r sidual liquid s parat d by the first evaporator may contain a small amount of feedstock (a dialkyl carbonat and/or an aromatic hydroxy compound), an aromatic carbonate (an alkyl aryl carbonate and/or a diaryl carbonate) and other high boiling point by-products in addition to the catalyst compon int.

In the m thod according to this third aspect, when part or all of th catalyst present in the s cond continuous multi-stage distillation column is in a state dissolved in the liquid phas, it is pref rred to introduce th

high boiling point r action mixture withdrawn in liquid form from the lower portion of the s cond distillation column to a second evaporator to effect a separation of the reaction mixtur into an vaporated component containing a diaryl carbonate represented by

and a residual liquid having the catalyst dissolved therein, and thereafter to recycle part or all of the residual liquid containing the dissolved catalyst to the second continuous multi-stage distillation column.

The residual liquid separated by the second evaporator may contain a small amount of each of an aromatic hydroxy compound, an alkyl aryl carbonate, a diaryl carbonate and other high boiling point by-products, in addition to the catalyst component.

Such catalyst separation and recycling steps may be applied to either one or both of the high boiling point reaction mixture withdrawn in liquid form from the lower portion of the first continuous multi-stage distillation column and the high boiling point reaction mixture withdrawn in liquid form from the lower portion of the second continuous multi-stage distillation colum.

When other high boiling point by-products than the desired products are contained in these residual liquids containing the catalyst, part or all of the residual liquids may be taken-out and subjected to treatment for removing the high boiling point by-products prior to recycling the residual liquids.

In the process of the present invention, the high boiling point reaction mixture containing the desired aromatic carbonate which is withdrawn from the lower portion of the continuous multi-stage distillation column, can be subjected to the conventional method for separation and purification, such as distillation, crystallization and the like, to thereby isolate the desired aromatic carbonate.

### Best Mode for Carrying Out the Invention

The present invention will be described in greater detail with reference to the following examples, which should not be construed as limiting the scope of the present invention.

### Example 1

5

10

20

30

35

A mixture of dimethyl carbonate, phenol and a catalyst was continuously fed in a liquid form to continuous multi-stage distillation column 1 at a position 1 m below the top thereof, which column was comprised of a packed column of 4 m in height and 3 inches in diameter and packed with a stainless steel-made Dixon packing (about 6 mm in diameter), from feeding pipe 2 through preheater 5 and conduit 6, as shown in Fig. 1. The thermal energy necessary for reaction and distillation was supplied by heating the liquid in the bottom of the distillation column with reboiler 10 and circulating the heated liquid through conduit 11. Reaction conditions are shown in Table 1. The liquid containing the catalyst and containing methyl phenyl carbonate and diphenyl carbonate as reaction products was continuously withdrawn from bottom 18 of the distillation column through conduits 8 and 19. Results of the reaction are shown in Table 1. The reaction liquid (reaction mixture) contained 0.02 % by weight of anisol which was considered to have been formed by side reaction (decarboxylation reaction) of methyl phenyl carbonate. These results show that the selectivity for anisol relative to the phenol is 0.8 %. Gas distilled from conduit 12 disposed at top 17 of the column was condensed by means of condenser 13. A portion of the resultant condensate was recycled into distillation column 1 through conduit 15, and the rest of the condensate was continuously withdrawn through conduit 16. From the condensate, methanol was obtained as a low boiling point reaction product.

### Comparative Example 1

12.6 kg of a mixture having the same composition as used in Example 1 was charged from feeding pipe 61 into autoclave type tank reactor 62 having a capacity of 15 liters and provided with distillation column 63 of 1 m in height and 1 inch in diameter [packed with a stainless ste I-mad Dixson packing (about 6 mm in diameter)] and stirrer 71 as shown in Fig. 6. Tank reactor 62 was h ated by means of electric furnace 70, while stirring, so as to keep the temperatur of the mixture constant at 204 °C, there by perform reaction. The gas distilled from top 69 of distillation column 63 was led through conduit 64 into condenser 65, in which condensation was affect d. A portion of the resultant condensate was recycled through conduits 66 and 67, and the

r st of th condensate was continuously withdrawn at a rat of 2.1 kg/hr through conduit 68. Reflux ratio was 0.8. At the time wh n 4.2 kg of condensate was withdrawn, tank reactor 62 was cooled and the reaction mixture was withdrawn through conduit 72. The quantity of the withdrawn liquid was 8.4 kg. The ratio of the quantity of the liquid remaining in the tank reactor to that charged into the tank reactor in this Comparative Example was the same as the ratio of the quantity of the column bottom liquid withdrawn through conduit 19 to the quantity of the liquid fed through conduit 6 in Example 1. The distillation rates of the distillates formed by condensing the gaseous components were also the same. Analyses showed that the reaction mixture contained 1.8 % by weight of methyl phenyl carbonate, 0.01 % by weight of diphenyl carbonate and 0.07 % by weight of anisol. The amount of product obtained per kg of the reaction mixture and per hour was 9 g/kg·hr for methyl phenyl carbonate and 0.05 g/kg·hr for diphenyl carbonate. The selectivity of the aromatic carbonate based on the phenol converted was 94 % for methyl phenyl carbonate and 1 % for diphenyl carbonate. The selectivity of the by-produced anisol based on the phenol converted was 5 %. When substantially the same reaction as mentioned above was conducted for 4 hr, the selectivity of the by-produced anisol changed to 7 %.

From the results of Example 1, in which the production rate of methyl phenyl carbonate was 34 g/kg·hr (97 % in selectivity), that of diphenyl carbonate 0.5 g/kg·hr (2 % in selectivity) and the selectivity of the by-produced anisol was 0.8 % (constant independently of the lapse of the reaction time), it is apparent that the method of the present invention is an excellent method which can produce an aromatic carbonate not only at a high reaction rate in a high yield (high productivity per unit time) with a high selectivity but also in a continuous fashion, as compared with the method (Comparative Example 1) in which a batch type tank reactor provided only with a distillation column at an upper portion thereof is used.

### Examples 2 to 4

15

Using the same apparatus as in Example 1, the reaction was carried out under the reaction conditions shown in Table 1. Results are shown in Table 1.

### Example 5

A mixture of dimethyl carbonate, phenol and a catalyst was continuously fed in a liquid form to continuous multi-stage distillation column 1 at a position 1 m below the top thereof, which column was comprised of a packed column of 4 m in height and 3 inches in diameter and packed with a stainless steel-made Dixon packing (about 6 mm in diameter), from feeding pipe 2 through preheater 5, as shown in Fig. 2. Simultaneously, dimethyl carbonate (which may contain a small amount of phenol) was introduced from feeding pipe 8' so as to continuously feed the same through evaporator 10' into the bottom portion of distillation column 1 in a gaseous form. Reaction conditions are shown in Table 2. High boiling point reaction products containing methyl phenyl carbonate and diphenyl carbonate as reaction products were continuously withdrawn from the bottom of the column through conduit 19. Gas distilled from the top of the column was led through conduit 12 into condenser 13 in which the gas was condensed. Methanol as a low boiling point product, was obtained from the liquid which was continuously withdrawn through conduit 16. Results of the reaction are shown in Table 2.

## Examples 6 to 9

Using the same apparatus as in Example 5, the reaction was carried out under the reaction conditions shown in Table 2. Results are shown in Table 2.

## Example 10

45

50

55

A reaction was carried out in substantially the same manner as described in Example 5, except that a 20-stage plate column of 6 m in height and 10 inches in diameter provided with sieve trays was used instead of a packed column as a continuous multi-stage distillation column as shown in Fig. 2 and the reaction was conducted under the reaction conditions indicated in Table 2. The feedstock mixture and catalyst to be introduced from feeding pipe 2 through preheater 5 were continuously fed to the column at a position 0.5 m below the top thereof. R sults are shown in Table 2.

### Example 11

Air action was continuously carried out in substantially the same manner as described in Example 1 except that a mixture of methyl phinyl carbonate and a catalyst was continuously fed institude of a mixture of

dimethyl carbonate, phenol and a catalyst, and that the reaction was conducted und r the reaction conditions indicated in Tabl 3. As a consequence of the reaction, from column bottom 18 of the continuous multi-stage distillation column, a column bottom liquid containing catalyst components and diphenyl carbonate as a desired product was continuously withdrawn through conduit 19. A condensate of gaseous components from the column top was continuously withdrawn through conduit 16. This condensate contained a small amount of anisol, and the other component of the condensate was dimethyl carbonate as a low boiling point reaction product. The selectivity of the by-produced anisol based on the methyl phenyl carbonate converted was 0.7 %. Results of the reaction are shown in Table 3.

10

15

### Comparative Example 2

To the same apparatus used in Comparative Example 1, 12.6 kg of a mixture of the same composition as used in Example 11 was charged through conduit 61. A reaction was conducted in substantially the same manner as described in Comparative Example 1, except that the liquid temperature was maintained at 195 °C during the reaction by heating tank reactor 62 by means of electric furnace 70 while stirring, that a condensate of gaseous components from the column top was continuously withdrawn through conduit 68 at a rate of 1.0 kg/hr, and the reflux ratio was 2.1. The reaction was carried out for 3 hours from the start of the withdrawal, and 3.0 kg of condensate was withdrawn. After cooling tank reactor 62, the reaction mixture was withdrawn through conduit 72, which weighed 9.6 kg. The ratio of the amount of withdrawn condensate to that of withdrawn liquid from the tank reactor in this comparative example was the same as the ratio of the amount of withdrawn condensate from the column top to that of withdrawn liquid from the column bottom in Example 11. Analyses showed that the reaction mixture contained 67.3 % by weight of diphenyl carbonate. The amount of diphenyl carbonate produced per kg of the reaction mixture and per hour was 224 g/kg-hr. The selectivity of the diphenyl carbonate based on the methyl phenyl carbonate converted was 95 %. By the analysis of the condensate from the column top, by-produced anisol was detected. The selectivity of the anisol based on the methyl phenyl carbonate converted was 5 %. Comparison of this result with the result obtained in Example 11 shows that diaryl carbonate can be produced at a higher yield and with a higher selectivity according to the process of the present invention.

30

### Examples 12 to 17

Using the same apparatus used in Example 11, the experiment was carried out under the reaction conditions indicated in Table 3. Results are shown in Table 3.

35

### Example 18

Using the same apparatus used in Example 5, a reaction was carried out in substantially the same manner as described in Example 5 by continuously feeding a mixture of methyl phenyl carbonate and a catalyst from feeding pipe 2 through preheater 5, and further introducing methyl phenyl carbonate from feeding pipe 8' so as to continuously feed through evaporator 10' and conduit 11 to the column bottom of distillation column 1 in a gaseous form. Reaction conditions are indicated in Table 4. A liquid containing diphenyl carbonate as a reaction product was continuously withdrawn from the bottom of the continuous multi-stage distillation column. Further, the gas distilled from the top of the column was condensed by means of condenser 13, and continuously withdrawn through conduit 16. From the thus obtained condensate, dimethyl carbonate was obtained as a low boiling point reaction product. Results are shown in Table 4.

Examples 19 to 20

50 Using the san

Using the same apparatus as used in Example 18, a reaction was carried out under the reaction conditions indicated in Table 4. Results are shown in Table 4.

In Example 19, the reaction was carried out by introducing phenol from feeding pipe 8'. As a result, methanol and dimethyl carbonate were contained in the condensate from the top of the column.

### 55 Example 21

A reaction was carri d out in substantially the same manner as described in Example 18, except that the sam plat column used in Exampl 10 was us d as a continuous multi-stage distillation column, that a fe d-stock and a catalyst wer continuously fed into the column at a position 0.5 m below the top thereof, and the

reaction conditions w re as shown in Table 4. Results are shown in Table 4..cp5

Exampl 22

5

10

15

30

(Preparation of catalyst)

20 kg of diphenyl carbonate and 4 kg of lead monoxide were heated at 180 °C for 5 hours to evolve carbon dioxide gas. Then, the most part of the remaining diphenyl carbonate was distilled off under a pressure of 1,3 kPa (10 mmHg), and the resultant product was allowed to cool down in a nitrogen atmosphere, thereby obtaining a catalyst (Catalyst A).

(Production of diphenyl carbonate)

An apparatus comprising two continuous multi-stage distillation columns as shown in Fig. 3 was employed. Reaction was performed by continuously feeding in a liquid form a mixture of dimethyl carbonate, phenol and Catalyst A to first continuous multi-stage distillation column 1' at a position 1 m below top 17 thereof, which column was comprised of a packed column of 4 m in height and 3 inches in diameter and packed with stainless steel-made Dixon packing (diameter: about 6 mm), from material feeding pipe 2 through conduit 4, preheater 5 and conduit 6, thereby allowing the mixture to flow down the inside of the first continuous multistage distillation column. The thermal energy necessary for reaction and distillation was supplied by circulating the column bottom liquid through conduits 8 and 9, reboiler 10 where heating was effected and conduit 11. The gas continuously distilled from column top 17 was led through conduit 12 to condenser 13 where the gas was condensed. A portion of the resultant condensate was recycled to first continuous multi-stage distillation column 1' through conduits 14 and 15 and the rest of the condensate was continuously withdrawn through conduit 16. From the withdrawn condensate, a low boiling point component containing methanol which was a low boiling point reaction product was obtained. A high boiling point component containing the catalyst component and methyl phenyl carbonate was continuously withdrawn from column bottom 18 through conduits 8 and 19.

Next, reaction was performed by continuously feeding in a liquid form the liquid withdrawn from the bottom of the first reaction distillation column to second continuous multi-stage distillation column 20 at a position 1 m below column top 26, which column was comprised of a packed column of 4 m in height and 3 inches in diatemer and packed with stainless steel-made Dixon packing (diameter: about 6 mm), through conduit 19, thereby allowing the liquid to flown down the inside of the second continuous multi-stage distillation column. The thermal energy necessary for distillation was supplied by circulating the column bottom liquid through conduits 28 and 29, reboiler 30 where heating was effected, and conduit 31. In this second continuous multistage distillation column, the catalyst which had been used in the first continuous multi-stage distillation column for the formation of an alkyl aryl carbonate and which had not been separated, as such, was utilized as a catalyst for the formation of a diaryl carbonate. The gas containing dimethyl carbonate, which was continuously distilled from column top 26, was led through conduit 21 to condenser 22 where the gas was condensed. A portion of the condensate was recycled to second continuous multi-stage distillation column 20 through conduits 23 and 24. The rest of the condensate was continuously withdrawn through conduits 23 and 25 and recycled to first continuous multi-stage distillation column 1' through conduit 4, preheater 5 and conduit 6. A high boiling point component containing the catalyst and diphenyl carbonate was continuously withdrawn from bottom 27 of second continuous multi-stage distillation column 20 through conduits 28 and 32. The conditions for reaction and the results attained after the steady state, are shown in Table 5.

Example 23

50 (Preparation of catalyst)

20 kg of phenol and 4 kg of dibutyltin oxide were heated at 180 °C for 10 hours while distilling off water being formed together with phenol. Then, the most part of the remaining phenol was distilled off under atmospheric pressure, and the r sultant product was allowed to cool in a nitrogen atmosphere, thereby obtaining a catalyst (Catalyst B).

(Production of diphenyl carbonat )

Using th sam apparatus as in Exampl 22, substantially the same proc dure as in Exampl 22 was per-

formed except that Catalyst B was employed instead of Catalyst A. The r action conditions and the results attained after the steady state had been reached, are shown in Tabl 5.

#### 5 Example 24

(Preparation of catalyst)

20 kg of methyl phenyl carbonate and 4 kg of plumbous acetate were heated at 180 °C for 10 hours. Then, the most part of the remaining methyl phenyl carbonate was distilled off under a pressure of 13 kPa (100 mmHg), and the resultant product was allowed to cool in a nitrogen atmosphere, thereby obtaining a catalyst (Catalyst C).

(Production of diphenyl carbonate)

15

10

The apparatus shown in Fig. 4 was employed. Reaction was performed by continuously feeding in a liquid form a mixture of dimethyl carbonate, phenol and Catalyst C to first continuous multi-stage distillation column 1' at a position 1 m below column top 17, which column was comprised of a packed column of 4 m in height and 3 inches in diameter and packed with stainless steel-made Dixon packing (diameter: about 6 mm), from material feeding pipe 2 through conduit 4, pre-heater 5 and conduit 6, thereby allowing the mixture to flow down the inside of first continuous multi-stage distillation column 1'. The thermal energy necessary for reaction and distillation was supplied by circulating through conduit 9', evaporator 10' where heating was effected and conduit 11, a portion of the dimethyl carbonate-containing low boiling point component returned from second continuous multi-stage distillation column 20 described below, together with fresh dimethyl carbonate fed from feeding pipe 8'. The gas distilled from column top 17 was led through conduit 12 to condenser 13 where the gas was condensed, and the condensate was continuously withdrawn through conduit 16. From the condensate, a low boiling point reaction mixture containing methanol which was a reaction product was obtained. A high boiling point reaction mixture containing methyl phenyl carbonate and catalyst components was continuously withdrawn from column bottom 18 through conduit 19.

Next, a reaction was performed by continuously feeding in a liquid form the liquid withdrawn from the bottom of first continuous multi-stage distillation column 1' to second continuous multi-stage distillation column 20 at a position 1 m below column top 26, which column was comprised of a packed column of 4 m in height and 3 inches in diameter and packed with stainless steel-made Dixon packing (diameter: about 6 mm), through conduit 19, thereby allowing the liquid to flow down the inside of second continuous multi-stage distillation column 20. The thermal energy necessary for distillation was supplied by circulating the column bottom liquid through conduits 28 and 29, reboiler 30 where heating was effected, and conduit 31. In this second continuous multi-stage distillation column 20, the catalyst used in first continuous multi-stage distillation column 1' for the formation of an alkyl aryl carbonate and which had not been separated, was utilized as it was, as a catalyst for the formation of a diaryl carbonate. The gas containing dimethyl carbonate, which was continuously distilled from column top 26, was led through conduit 21 to condenser 22 where the gas was condensed. Aportion of the condensate was recycled to second continuous multi-stage distillation column 20 through conduits 23 and 24. The rest of the condensate was continuously withdrawn through conduits 23 and 25 and recycled to first continuous multi-stage distillation column 1' through conduits 3 and 4, preheater 5 and conduit 6. A portion of the condensate withdrawn through conduit 25 was recycled to the lower portion of continuous multi-stage distillation column 1' through conduit 7 and evaporator 10'. A high boiling point reaction mixture containing the catalyst component and diphenyl carbonate was continuously withdrawn from bottom 27 of second continuous multi-stage distillation column 20 through conduits 28 and 32. The reaction conditions and the results attained after the steady state, are shown in Table 5.

## 50 Example 25

Using the same apparatus as in Example 24, substantially the same procedure as in Example 24 was performed except that p-cresol was employed instead of phenol. The reaction conditions and the results attained after the steady stat , are shown in Table 5.

Exampl 26

Using the same apparatus as in Example 24, substantially the same procedure as in Example 24 was performed except that dilthyl carbonat was employed instead of dimethyl carbonat. The reaction conditions

and the results attained after the steady state, are shown in Table 5.

Exampl 27

(Preparation of catalyst)

15 kg of phenol, 5 kg of methyl phenyl carbonate, and 4 kg of dibutyltin oxide were heated at 180 °C for 10 hours while distilling off water being formed together with phenol. Then, the most part of each of the remaining phenol and the remaining methyl phenyl carbonate was distilled off under atmospheric pressure, and the resultant product was allowed to cool in a nitrogen atmosphere, thereby obtaining a catalyst (Catalyst D).

(Production of diphenyl carbonate)

Using the same apparatus as in Example 24, substantially the same procedure as in Example 24 was performed except that Catalyst D was employed instead of Catalyst C. The reaction conditions and the results attained after the steady state, are shown in Table 5.

Example 28

20

5

10

15

Using the same apparatus as in Example 24, substantially the same procedure as in Example 24 was performed except that tetraphenoxy titanium was employed instead of Catalyst C. The reaction conditions and the results attained after the steady state, are shown in Table 5.

Example 29

(Preparation of catalyst)

20 kg of phenol and 4 kg of lead monoxide were heated at 180 °C for 10 hours while distilling off water being formed together with phenol, thereby obtaining a catalyst (Catalyst E).

(Production of diphenyl carbonate)

An apparatus as shown in Fig. 5 was employed. Reaction was performed by continuously feeding in a liquid form a mixture of dimethyl carbonate, phenol and Catalyst E to first continuous multi-stage distillation column 1' at a position 0.5 m below column top 17, which column was comprised of a 20-plate column of 6 m in height and 10 inches in diameter and provided with sieve trays, from material feeding pipe 2 through conduits 4 and 39, preheater 5 and conduit 6, thereby allowing the mixture to flow down the inside of the first continuous multi-stage distillation column 1'. The thermal energy necessary for reaction and distillation was supplied by heating with evaporator 10' a portion of the low boiling point reaction mixture returned from second continuous multi-stage distillation column 20 described below through conduits 24, 25 and 7, together with fresh dimethyl carbonate fed from feeding pipe 8' and through conduit 9', and circulating the heated mixture through conduit 11. The gas distilled from column top 17 was led through conduit 12 to condenser 13 where the gas was condensed, and the condensate was continuously withdrawn through conduit 16. From the withdrawn condensate, a low boiling point reaction mixture containing methanol which was a low boiling point reaction product was obtained. The reaction mixture continuously withdrawn from column bottom 18 was introduced into evaporator 33 through conduit 19. The residual liquid in evaporator 33 containing the catalyst for the formation of methyl phenyl carbonate was returned from the bottom of evaporator 33 to first continuous multi-stage distillation column 1' through conduits 34, 38 and 39, preheater 5 and conduit 6. The feeding of catalyst E through conduit 2 was stopped at the time when the concentration of the catalyst being recycled had reached a predetermined value.

The vaporized product containing methyl phenyl carbonate generated in evaporator 33 by circulating a portion of the residual liquid flowing out of evaporator 33 through conduit 34, to evaporator 33 through conduit 35, reboil r 36 and conduit 37, was continuously f d to second continuous multi-stag distillation column 20 compris d of a plat column f 6 m in height and 10 inches in diameter and provided with a 20-stag sieve tray, through conduit 40 and from feeding pipe 41 position d 1.5 m below column top 26. The catalyst (Catalyst E) for the formation of diaryl carbonate was continuously fed in a liquid form to second continuous multi-stage distillation column 20 through conduit 51 and from feeding pipe 48 positioned 1.5 m below the column top. The most part of the gaseous methyl phenyl carbonate fed to second continuous multi-stage distillation column

20 is liquefied in the column and the resultant liquid flows down the inside of the column together with the catalyst, thereby effecting the r action. The thermal nergy n cessary for reaction and distillation was suppli d by circulating th column bottom liquid from column 20 through conduits 28 and 29, reboiler 30 where th liquid was heat d, and conduit 31 so that th liquid was return d to column 20. Alow boiling point reaction mixture containing dimethyl carbonate and continuously distilled from column top 26 was led through conduit 21 to condenser 22 where condensation was effected. A portion of the resultant condensate was recycled to second continuous multi-stage distillation column 20 through conduits 23 and 24. The rest of the condensate was continuously withdrawn through conduits 23 and 25 and recycled to first continuous multi-stage distillation column 1' through conduits 3, 4 and 39, preheater 5 and conduit 6. A portion of the condensate continuously withdrawn through conduit 25 was recycled to the lower portion of first continuous multi-stage distillation column 1' through conduits 7 and 9', evaporator 10' and conduit 11. A high boiling point reaction mixture containing the catalyst and diphenyl carbonate and which was continuously withdrawn from bottom 27 of second continuous multi-stage distillation column 20 was introduced to second evaporator 42 through conduits 28 and 32. The vaporized product generated in evaporator 42 by circulating a portion of the residual liquid flowing out of evaporator 42 through conduit 43, to evaporator 42 through conduit 44, reboiler 45 and conduit 46, was continuously withdrawn in a liquid form through conduit 52, condenser 49 and conduit 50. The vaporized product contained diphenyl carbonate as the main ingredient. The residual liquid in evaporator 42 containing the c atalyst for the formation of diaryl carbonate was recycled from the bottom of evaporator 42 to second continuous multi-stage distillation column 20 through conduits 43, 47 and 48. The feeding of catalyst E through conduit 51 was stopped when the concentration of the catalyst being recycled had reached a predetermined value. The flow rates and the compositions at portions of the apparatus are shown in Table 6. The reaction conditions and the results attained after the steady state had been reached, are shown in Table 7.

### 25 Example 30

35

45

(Preparation of catalyst)

 $5 \, \mathrm{kg}$  of  $\gamma$ -alumina (manufactured and sold by Nikki Co., Japan; Product No.611N) was packed into a cylinder made of quartz glass (length: 100 cm; diameter:10 cm) and the cylinder was placed in a tubular furnace. The inside of the furnace was flushed with nitrogen and the furnace was heated at 200 °C for 5 hours, thereby drying the  $\gamma$ -alumina. Next, into the cylinder, which had been heated to 200 °C, was introduced a (20 wt%) benzene solution of tetramethoxy silane for 10 hours at a flow rate of 50 ml/hr, thereby treating the  $\gamma$ -alumina. The thus treated product was allowed to cool down in a nitrogen atmosphere, thereby obtaining a catalyst (Catalyst F).

### (Production of diphenyl carbonate)

Substantially the same procedure as in Example 24 was performed except that a packed column of 2 m in height and 1.5 inches in diameter and packed with Catalyst F was employed as each of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column. The reaction conditions and the results attained after the steady state had been reached, are shown in Table 5.

### Comparative Example 3

Into the same apparatus as used in Comparative Example 1, which apparatus is shown in Fig.6, charged through conduit 61 was 12.8 kg of a mixture of the same composition as used in Example 23. Reaction was effected in substantially the same manner as in Comparative Example 1 by heating tank reactor 62 by means of electric furnace 70, while stirring, except that the temperature of the reaction mixture was kept constant at 202 °C and that the condensate was continuously withdrawn through conduit 68 at a rate of 1.0 kg /hr. At the time when the amount of the condensate withdrawn from the reactor had become 12.1 kg, tank reactor 62 was cooled down and the reaction mixture was withdrawn through conduit 72. The quantity of the withdrawn reaction mixture was 0.7 kg. The ratio of the quantity of the reaction mixture remaining in the tank reactor to that charg d into the tank reactor in this Comparative Exampl 3 was th same as th ratio of th quantity of the column bottom liquid withdrawn through conduit 28 to th quantity of the liquid fed through conduit 6 in Example 23. Analysis show d that the reaction mixture c ntained 14.0 % by weight of formed diph nyl carbonat. The amount of diphenyl carbonate formed per kg of the reaction mixture and per hour was 12 g/kg-hr. Th selectivity of the diphenyl carbonate based on the phenol converted was 83 %. Analysis of the column top condensate showed that anisol had b en by-produced with a selectivity of 8 % based on the phenol converted was 83 on the phenol converted was 83 was do not the phenol converted was 83 was do not the phenol converted was 83 on th

vert d.

Comparison of the abover sults with their sults of Example 23 (the production rate of diphenyl carbonate: 524 g/kg·hr; selectivity: 95 %) shows that the method of the present invention is an excellent method which can produce diphenyl carbonate not only at a high reaction rate with a high selectivity in a high yield but also in a continuous fashion.

EP 0 461 274 B1

|                                       |                            |              |               |                |                    | _                     |        |     |        |            |        |     |              |            | _      |     |        |              |        |     |            |
|---------------------------------------|----------------------------|--------------|---------------|----------------|--------------------|-----------------------|--------|-----|--------|------------|--------|-----|--------------|------------|--------|-----|--------|--------------|--------|-----|------------|
| 5                                     |                            | <b>3</b>     | Select-       | 6 1 1 A 1 C A  | Type (%)           | MPC                   | (16)   | DPC | (2)    | ) J.W      | (41)   | DTC | (3)          | Oda        | (96)   | DPC | (3)    | OdW          | (86)   | DPC | <b>(E)</b> |
| 10                                    | Aromatic                   |              | Amo un t      | o i<br>Product | Type (g/kg.hr)     | MPC                   | (34)   | DPC | (0.5)  | MTC        | (42)   | DTC | (0.7)        | EPC        | (42)   | DPC | (0.9)  | MPC          | (20)   | DPC | (0.4)      |
|                                       | - lod n                    | uit19)       | Compo-        | 0 1 1 5        | Type<br>(wt%)      | MPC                   | (3.4)  | DPC | (0.02) | ЭДИ        | (4.2)  | DTC | (0.01)       | EPC        | (4.2)  | DPC | (0.03) | MPC          | (2.0)  | DPC | (0.04)     |
| 15                                    | Column                     |              | Flow          | 4<br>5         | kg/hr              | 4.2                   |        |     |        | 2.9        |        |     |              | 3.5        |        |     |        | 2.3          |        |     |            |
| 20                                    | Conden-<br>sate            | (conduit 16) | F. 10 W       | 9              | kg/hr              | 2.1                   |        |     |        | 1.3        |        |     |              | 1.3        |        |     |        | 1.1          |        |     |            |
| 25                                    |                            | Re-          | flux          | =              |                    | 8.0                   |        |     |        | 1.5        | _      |     |              | 1.2        |        |     |        | 1.0          |        |     |            |
| % % % % % % % % % % % % % % % % % % % | Reaction<br>conditions     | ပ            | Sure at       | top            | kg/cm <sup>2</sup> | 8                     |        |     |        | <b>∞</b>   |        |     |              | <b>∞</b>   |        |     |        | <del>~</del> |        |     |            |
| es<br>∐<br>35                         | Α<br>2                     | Temper       |               | bot tom        | ပ                  | 204                   |        |     |        | 203        |        |     |              | 203        |        |     |        | 201          |        |     |            |
| 40                                    | g pipe 2<br>n              |              | Catalyst      |                | Type<br>(mmol/kg)  | Pb (0Ph) <sub>2</sub> | (6.3)  |     |        | Pb (OPh) 2 | (9.5)  |     |              | Pb (0Ph) 2 | (8.7)  |     |        | Ti (OPh)     | (13.5) |     |            |
| <b>4</b> 5                            | rom feeding<br>Composition | Aromatic     |               | ,              | Type<br>(wt%)      | PhoH                  | (36.8) |     |        | p-cresol   | (42.3) |     |              | PhoH       | (43.7) |     |        | PhoH         | (33.7) |     |            |
| 50                                    | j d                        | Dialkyl      | carbonate     |                | Type<br>(wt%)      | DMC                   | (73.2) |     |        | DMC        | (57.7) |     |              | DEC        | (56.3) |     |        | DMC          | (66.3) |     |            |
| 55                                    | ╼├─                        |              | rale<br>kg/hr |                |                    | 6.3                   |        |     |        | 7.5        |        |     | <br> -<br> - |            |        |     | 1      | ٠.<br>4.     |        |     |            |

Exam-ple

~

က

| 5  |                          |                    |                                                                                                                                   |        |                       |                    |                      |                     |                     |                  |                   |           |        | upled                                                                |                                     | , o f                                                                      | •                                                | rity of the aromatic carbonate is calculated, based on the aromatic hydroxy |                          |
|----|--------------------------|--------------------|-----------------------------------------------------------------------------------------------------------------------------------|--------|-----------------------|--------------------|----------------------|---------------------|---------------------|------------------|-------------------|-----------|--------|----------------------------------------------------------------------|-------------------------------------|----------------------------------------------------------------------------|--------------------------------------------------|-----------------------------------------------------------------------------|--------------------------|
| 10 |                          |                    |                                                                                                                                   |        |                       |                    |                      |                     |                     |                  |                   |           |        | ctively co                                                           |                                     | s of grams                                                                 |                                                  | the aromat                                                                  |                          |
| 15 |                          |                    |                                                                                                                                   |        |                       |                    |                      |                     |                     |                  |                   |           |        | ICP (indu                                                            |                                     | d in term                                                                  | ur.                                              | based on                                                                    |                          |
| 20 |                          |                    |                                                                                                                                   |        |                       |                    |                      |                     |                     |                  |                   |           |        | ns of an                                                             |                                     | expresse                                                                   | nd per ho                                        | culated,                                                                    |                          |
| 25 |                          |                    |                                                                                                                                   |        |                       |                    |                      |                     |                     |                  |                   |           |        | ed by mea                                                            |                                     | bonate is                                                                  | liquida                                          | te is cal                                                                   |                          |
| 30 |                          |                    |                                                                                                                                   |        |                       |                    | ıt e                 | a                   | a)                  |                  |                   |           |        | determin                                                             | /zer).                              | omatic car                                                                 | ımı dottom                                       | ic carbona                                                                  | rerted.                  |
| 35 |                          | r bonat e          | bonate                                                                                                                            |        | e a d                 | raphenoxy titanium | hyl phenyl carbonate | hyl tolyl carbonate | yl phenyl carbonate | rbonate          | bonate            |           |        | concentration was determined by means of an ICP (inductively coupled | tral anal)                          | oduced are                                                                 | per kg of the column bottom liquid and per hour. | he aromat                                                                   | raw material, converted. |
| 40 | lbols>                   | dimethyl carbonate | diethyl carbonate                                                                                                                 | phenol | diphenoxy lead        | traphenox          | thyl phen            | thyl toly           | hyl pheny           | phenyl carbonate | ditolyl carbonate | by weight |        |                                                                      | plasma emission spectral analyzer). | amount of the produced aromatic carbonate is expressed in terms of grams o |                                                  | ivity of t                                                                  |                          |
| 45 | s ya                     | Đ.                 | <del>-</del> | 4      | <u>-</u>              | t e t              | Be -                 | ne t                | e t h               | d i þ            | Ð                 | <b>%</b>  |        |                                                                      | =                                   | nt                                                                         | O n                                              | 7                                                                           |                          |
|    | 0 f                      | ••                 | ••                                                                                                                                | ••     | ••                    | ••                 | ••                   | ••                  | ••                  | ••               | ••                | ••        |        | catalyst                                                             | 1a e                                | U O III                                                                    | product                                          | ele                                                                         | on (                     |
| 50 | (Description of symbols) | DMC                | DEC                                                                                                                               | PhoH   | Pb (0Ph) <sub>2</sub> | Ti (0Ph) 4         | MPC                  | MTC                 | EPC                 | DPC              | DTC               | w 1 %     | e)     | 1. The c                                                             | plasn                               | 2. The a                                                                   | the                                              | 3. The selectiv                                                             | compound, a              |
|    | (Des                     | :                  |                                                                                                                                   |        |                       |                    |                      |                     |                     |                  |                   |           | (Note) |                                                                      |                                     |                                                                            |                                                  |                                                                             |                          |

EP 0 461 274 B1

| 5  |         | matic       | carbonate   | R. 1 0.00      | -<br>-<br>- | · .       | Type                   | MPC      | (97)   | OPC<br>(2)   | MPC        | (97)  | 0PC<br>(2)     | MPC           | (86)<br>(86) | <b>3</b> 3 | MTC         | (97)     | (2)       | EPC          | (97)     | 360             | MPC          | DPC<br>(2) |
|----|---------|-------------|-------------|----------------|-------------|-----------|------------------------|----------|--------|--------------|------------|-------|----------------|---------------|--------------|------------|-------------|----------|-----------|--------------|----------|-----------------|--------------|------------|
| 10 |         | Aroma       | Car         | A a c a d      | П           | _         | Type (g                | MPC      | (81)   | 3) DPC       | -          | (93)  |                | -             | _            | (0.6)      | _           | (72)     | 3         | EPC          | <u> </u> | )<br>(1)<br>(1) | MPC          | DPC<br>(2) |
| 15 |         | Column bot- | idui        | (conduitly)    | Flow Compo  |           | Type (with             | 0        | (8.7)  | DPC<br>(0.13 | 2.9 MPC    | (6.3) | (0.1;<br>(0.1; | 3.3 MPC       | (6.8)        | (0.06      | 2.9 MTC     | (7.2)    | (0.5)     | 3.2 EPC      | (7.1)    | (0.1)           | 34.1 MPC     | DPC (0.2)  |
| 20 |         | Conden- (   |             | -npu00)        | Flow        |           | 1 1 1 1 1              | 2.3      |        |              | 2.4        |       |                | 2.1           |              |            | 1.4         |          |           | 1.3          |          |                 | 36.6 3       |            |
| 25 | _,      | ction       | itions      | rres Ke-       | at          | o lumnt   | 1 0 p                  | 1        |        |              | 0<br>8     |       |                | 0<br><b>%</b> |              |            | <del></del> |          |           | 0 8          |          |                 | 0 8          |            |
| 30 | b 1 e 2 | _           | <b>−</b>  E | i crature      | at          | dco i umn | bot ton                | 205      |        |              | 202        |       |                | 502           |              |            | 203         |          |           | 203          |          |                 | 203          |            |
|    | Tat     | · ·         | b i b       | 1 A romat      | . 1         | compoun   | Type                   | <u></u>  | (11.2) |              | 1          |       |                | Ph.           | _            |            | <u>d</u>    | <u> </u> |           |              |          |                 | PhOH (13, 5) |            |
| 35 |         | ed li       | eeding      | WDialky        | 6<br>2      | a t e     | Type<br>(wt%)          | 1 DMC    | (88.8) |              | DMC        | (100) |                | OFFC<br>OFFC  | (85.5        | $\dashv$   | 2 DMC       | (30.0)   |           | 2 DEC        | (100)    |                 | 2 DMC (86.5) |            |
| 40 | į       | <u> </u>    |             | T <sub>e</sub> | yst rat     |           | ) e   kg/<br>/kg)   hr | Ph) 2 3. | <br>   |              | (0Ph) 2 3. | <br>6 |                | s SnO 3.      | <br>જે       |            | (OPh) 2 2.  |          |           | b (OPh) 2 2. |          |                 | (OPh) 246.   |            |
| 45 |         |             | ۔ انہ       | 10 0           | Catal       | -         | Typ<br>(mmo)           | P.       |        | _            | P (        | උ<br> | -              | <u>B</u>      |              | _          | ፈ`          |          |           | ۵.           |          | _               | 2<br>-       |            |
| 50 |         | liqui       | Compos      | ′⊨≃            | 1           | componu   | 1ype<br>(#1%)          | `        |        |              | PhoH       |       |                |               | (34.6        |            | P-creso!    |          |           | Phody        |          | - 1             | PhoH (45.8)  |            |
| 50 |         | Feed        | l e e d     | lowDialky      | atecarbon   | a t e     | 1 y p e<br>(w t %)     | ā,       | (54.7) | 1            | Z DMC      | 0.667 |                |               | (43.3)       |            | II DMC      | -        | - 1       | DEC          | (56.3    |                 | (54.2)       |            |
| 55 |         |             | 1_          | Exam-Flo       | le rat      |           | ж<br>87<br>г           | 5 2.2    |        | _            | 2.2        |       | $\dashv$       | 7 2.4         |              | _          | <br>8       |          | $\exists$ | 9<br>        |          | l               | 0 24.5       | _          |
|    | - (     |             |             | <u>핍</u>       | <u>a</u>    |           |                        |          |        |              |            |       | [              |               |              |            |             |          |           |              |          |                 | 2            |            |

| 5  |                |                     |                   |        |                |                     |                         |                        |                        |                    |                   |             |
|----|----------------|---------------------|-------------------|--------|----------------|---------------------|-------------------------|------------------------|------------------------|--------------------|-------------------|-------------|
| 10 |                |                     |                   |        |                |                     |                         |                        |                        |                    |                   |             |
| 15 |                |                     |                   |        |                |                     |                         |                        |                        |                    |                   |             |
| 20 |                |                     |                   |        |                |                     |                         |                        |                        |                    |                   |             |
| 25 |                |                     |                   |        |                |                     |                         |                        |                        |                    |                   |             |
| 30 |                |                     |                   |        |                |                     | nate                    | ate                    | ate                    |                    |                   |             |
| 35 |                | dimethyl carabonate | diethyl carbonate |        | y lead         | dibutyl tin oxide   | methyl phenyl carbonate | methyl tolyl carbonate | ethyl phenyl carbonate | diphenyl carbonate | ditolyl carbonate | ght         |
| 40 | sympols)       | dimethyl            | diethyl           | phenol | diphenoxy lead | dibutyl             | methylp                 | methyl t               | ethyl ph               | diphenyl           | ditolyl           | % by weight |
| 45 | J o            | ••                  | ••                | ••     |                | ••                  | ••                      | ••                     | ••                     | ••                 | ••                | ••          |
| 50 | (Description o | DMC                 | DEC               | P hOH  | Pb (0Ph)       | Bu <sub>2</sub> SnO | MPC                     | MTC                    | EPC                    | DPC                | DTC               | ₩ t%        |

55

Note)

- The amount of the produced aromatic carbonate is expressed in terms of grams of the The catalyst concentration was determined by means of an ICP (inductively coupled plasma emission spectral analyzer). 3.
  - product per kg of the column bottom liquid and per hour.
- The selectivity of the aromatic carbonate is calculated, based on the aromatic hydroxy compound, a raw material, converted. . .

| 5 |  |
|---|--|
|   |  |

က

T a

|            |       | Cood Linuia        |                       | ٦        |            |       |              |        |               |                  |           |
|------------|-------|--------------------|-----------------------|----------|------------|-------|--------------|--------|---------------|------------------|-----------|
|            |       | בנים ביולחות       | 306                   | <b>~</b> | Reaction   |       | Condensate   | Co LEB | Column bottom |                  |           |
| _          |       | י ב ב חווו אין א ה | 7                     | ပ        | CONGILIONS | S     | ,            | Diabil | P             | Diaryl carbonate | rbonate   |
|            |       | Composi            | 틸                     | Tempe-   | Pres-      |       | (conduit 16) | (con   | (conduit 19)  |                  | •         |
| Exam-      |       | Alkyla             | Catalyst              | rature   | sure       | Re-   |              | Flow   | Compo-        | Amount of        | Select    |
| 9 <u>-</u> | rale  | carbonate          |                       | 3 t      | at         | flux  | Flow rate    | rate   | sition        |                  | , v : v : |
|            |       |                    |                       |          | column     | ratio |              |        |               |                  | :         |
| _          | kg/br | •                  | Type                  | bottom   | top        |       | kg/hr        | kg/hr  | 1             | TVDP             | ı         |
|            |       | (#1%)              | (mmol/kg)             |          | maHg       |       | ;            |        | (wt%)         | (g/kg·hr)        |           |
| =          | 4.2   | MPC                | Pb (0Ph) 2            | 195      | 194        | 2.1   | 1.0          | 3.2    | DPC           | DPC              |           |
|            |       | (66)               | (8.0)                 |          |            |       |              |        | (75.7)        | (757)            | (66)      |
| 12         | 4.2   | MPC                | Bu <sub>2</sub> SnO   | 194      | 199        | 2.0   | 1.2          | 3.0    | DPC           | DPC              | DPC       |
|            |       | (66)               | (12.8)                |          |            |       |              |        | (73.8)        | (738)            | (66)      |
| -13        | 4.0   | EPC                | Pb (0Ph) <sub>2</sub> | 198      | 241        | 2.3   | 1.1          | 2.9    | DPC           | DPC              | DPC       |
|            |       | (66)               | (10.5)                |          |            |       |              |        | (40.9)        | (602)            | (66)      |
| 4          | 4.3   | MTC                | 2 (440) 44            | 201      | 182        | 1.7   | 1.4          | 2.9    | DTC           | DTC              | DTC       |
|            |       | (88)               | (12.0)                |          |            |       |              |        | (77.3)        | (773)            | (66)      |
| 15         | 4.2   | MPC                | Ti (0Ph) 4            | 195      | 223        | 1.8   | 1.2          | 3.0    | DPC           | DPC              | DPC       |
|            |       | (66)               | (12.5)                |          |            |       |              |        | (70.5)        | (105)            | (66)      |
| 16         | 6.3   | MPC                | Pb (0Pb) 2            | 195      | 270        | 2.1   | 1.9          | 4.4    | DPC           | DPC              | DPC       |
|            |       | (82)               | (10.5)                |          |            |       |              |        | (61,8)        | (618)            | (66)      |
|            |       | PhoH               |                       |          |            |       |              |        | <b>&gt;</b>   |                  |           |
|            |       | (14)               |                       |          |            |       |              |        |               |                  |           |
| 17         | 4.2   | MPC                | Pb (0Pb) 2            | 194      | 91         | 2.1   | 1.4          | 3.4    | DPC           | DPC              | DPC       |
|            |       | (66)               | (40.0)                |          |            |       |              |        | (419)         | (013)            | (00)      |

| 5           |                                                                                                                                | ICP (inductively couple in terms of grams of the ed on the alkylaryl                                                                                                                                                                                          |
|-------------|--------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 10          |                                                                                                                                | (inductively couterns of grams of on the alkyl aryl                                                                                                                                                                                                           |
| 15          |                                                                                                                                | S                                                                                                                                                                                                                                                             |
| 20          |                                                                                                                                | means of an is expressed ind per hour.                                                                                                                                                                                                                        |
| 25          |                                                                                                                                | rmined by<br>arbonate<br>liquid a<br>nate is c<br>d.                                                                                                                                                                                                          |
| 30          | d xide titanium carbonate carbonate onate nate                                                                                 | lyst concentration was determined by means of an mission spectral analyzer).  nt of the produced diaryl carbonate is expressed per kg of the column bottom liquid and per hour. ctivity of the diaryl carbonate is calculate, bae, a raw material, converted. |
| <b>35</b> c | e a a c a c a c a c a c a c a c a c a c                                                                                        | entration pectral a produced the colu                                                                                                                                                                                                                         |
| 40          | symbols) diphenoxy lead dibutyl tin ox tetraphenoxy t methyl phenyl methyl tolyl c ethyl phenyl c diphenyl carbo ditolyl carbo | alyst concentration was detemission spectral analyzer) unt of the produced diaryl per kg of the column botto ectivity of the diaryl carb                                                                                                                      |
| 45          | (Description of Pb (OPh) 2: Bu2Sn0: Ti (OPh) 4: MPC: MTC: EPC: DPC: DTC: WT%:                                                  | The cataplasma e The amou product The sele                                                                                                                                                                                                                    |
| 50          | (Descrip<br>Pb (<br>Buz<br>Ti (<br>MPC<br>MTC<br>EPC<br>DPC                                                                    | (Note) 1. 2. 3.                                                                                                                                                                                                                                               |

EP 0 461 274 B1

| 5  |
|----|
| 10 |
| 15 |
| 20 |
| 25 |
| 30 |
| 35 |
|    |

| 1004                                                                             | 1001                                | Selec                          | ivity             | Type         |                 | DPC            | (66)   | DPC    | (66)   | DPC            | (66)   | DPC             | (66)   |
|----------------------------------------------------------------------------------|-------------------------------------|--------------------------------|-------------------|--------------|-----------------|----------------|--------|--------|--------|----------------|--------|-----------------|--------|
| Diary Carbona                                                                    | 90                                  | Compo- Amount of Selec         | product           | Type         | (#1%) (g/kg·hr) | DPC            | (468)  | DPC    | (523)  | DPC            | (504)  | DPC             | (525)  |
| bottom                                                                           | uit 19)                             | Compo-                         | sition            | Type         | (%1%)           | OPC            | (46.8) | DPC    | (52.3) | DPC            | (50.4) | DPC             | (52.5) |
| Column                                                                           | (cond                               | Flow                           | rate              | (kg/hr) Type |                 | 5.5            |        | 5.0    |        | 5.2            |        | 43.5            | i      |
| Condensate                                                                       | Tempe-Pres- (conduit16) (conduit19) |                                | Flow rate         | (kg/hr)      |                 | 3.2            |        | 3.7    |        | 2.8            |        | 28.0            |        |
| ion                                                                              | Pres-                               | sure                           | at at             | t o p        | BEETE           | 321            |        | 274    |        | 682            |        | 275             |        |
| React ion<br>conditions                                                          | Tempe-                              | rature                         | a t               | bot tomtop   | ر               | 192            |        | 190    |        | 191            |        | 190             |        |
| Feed liquid from Reaction Condensate Column bottom<br>feeding pipe 8' conditions |                                     | yst Flow Compositionraturesure |                   | Type         |                 | MPC            |        | PhOH   |        | MPC            |        | MPC             |        |
| Feed I                                                                           |                                     | FOW                            | rate              | (kg/br)      |                 | 4.5            |        | 1.3    |        | 2.0            |        | 37.0            |        |
| iquid from<br>g pipe 2                                                           | 1.                                  | Catalyst                       |                   | Type         | (SV / 1 0mm)    | Pb (OPb) 2 4.5 | (8.0)  | Bu2Sn0 | (12.8) | Pb (OPh) 2 2.0 | (10.5) | Pb (OPh) 2 37.0 | (13.5) |
| Feed liquid f<br>feeding pipe                                                    | Composition                         | AIKYI                          | ary!<br>carbonate | Type         |                 | MPC            | (66)   | MPC    | (66)   | MPC            | (66)   | MPC             | (66)   |
| Fe                                                                               |                                     |                                | 1 a 1 e           | kg/hr        |                 | 4.2            |        | 4.2    |        | 4.0            |        | 34.5            |        |
|                                                                                  |                                     | Exag-                          | э<br>-<br>-       |              |                 | <u>~</u>       |        | 19     |        | 20             |        | 21              |        |

| 5<br>10<br>15<br>20 |                                                                                                         | The catalyst concentration was determined by means of an ICP (inductively coupled plasma emission spectral analyzer).  The amount of the produced diaryl carbonate is expressed in terms of grams of the product per kg of the column bottom liquid and per hour.  The selectivity of the diaryl carbonate is calculated, based on the alkyl aryl carbonate, a raw material, converted. |
|---------------------|---------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 30<br>35            | symbols) phenol diphenoxy lead dibutyl tin oxide methyl phenyl carbonate diphenyl carbonate % by weight | The catalyst concentration was determined by means of an plasma emission spectral analyzer).  The amount of the produced diaryl carbonate is expressed product per kg of the column bottom liquid and per hour. The selectivity of the diaryl carbonate is calculated, b carbonate, a raw material, converted.                                                                          |
| <b>4</b> 5          | (Description of sy- PhOH : P Pb (OPh) 2 : d Bu 2 SnO : d MPC : m DPC : d wt % : %                       | 1. The cataly plasma emi 2. The amount product pe 3. The select carbonate,                                                                                                                                                                                                                                                                                                              |

|    |       |                          |                               |                |                  |                              |      |        |      |        |        |                    |        |      |            |       |               |        |    | _      |          |                |        |     | _     |              |
|----|-------|--------------------------|-------------------------------|----------------|------------------|------------------------------|------|--------|------|--------|--------|--------------------|--------|------|------------|-------|---------------|--------|----|--------|----------|----------------|--------|-----|-------|--------------|
| 5  |       |                          | l<br>nate                     | Selec-         | 1 1 A I { }      | Type<br>(%)                  | DPC  | (86)   |      |        |        |                    |        | DPC  | (38)       |       |               |        |    |        | Jag      | (36)           |        |     |       |              |
| 5  |       |                          | Diary                         | Amount         | o i<br>product   | Type<br>R/kgHr               | DPC  | (828)  |      |        |        |                    |        | DPC  | (254)      |       |               |        |    |        | DPC      | (926)          |        |     |       |              |
| 10 |       | a)                       | Column bot-                   | conduit 28)    | Composi-<br>tion | * i =                        | DPC  | (82.8) |      |        |        |                    |        | DPC  | (52.4)     |       | ,             |        |    |        | DPC      | (92.6)         |        |     |       |              |
|    |       | -5128                    | <u>ب</u>                      | <u>اره، ام</u> | B 0              | k 8/                         | 0.35 |        |      |        |        |                    |        | 0.35 |            |       |               |        |    |        | D. 81    |                |        |     |       |              |
| 15 |       | continuous multi-stage   | tions Condens-<br>ate (con-   | duit 25)       | rate             | kg/br                        | 3.7  |        |      |        |        |                    |        | 3.7  |            |       |               |        |    |        | 3.7      |                |        |     |       |              |
|    |       | tinuo<br>on co           | tions                         |                | ratio            |                              | 1.6  |        |      |        |        |                    |        | 1.6  |            |       |               |        |    |        | 1.5      |                |        |     |       |              |
| 20 |       | Second con<br>distillati | Reaction condi<br>Tempe-Pres- | sure           | co lomn          | top<br>mmHg                  | 300  |        |      |        |        |                    |        | 300  |            |       |               |        |    |        | 310      |                |        |     |       |              |
|    |       | S.<br>di                 | empe-                         | ature          | co luma          | Setta<br>C                   | 198  |        |      |        |        |                    |        | 197  |            |       |               |        |    |        | 195      |                |        |     |       |              |
| 25 | (1)   |                          | bot-<br>quid                  | conduit 19) fr | t ion            | *<br>*                       | MPC  | (10.9) |      |        |        | <del></del>        |        | MPC  | .3<br>(8.3 |       |               |        |    |        |          | (27.4)         |        |     |       |              |
|    |       |                          | O '                           | Sign           | 5 =              | \ <u>\</u>                   | 4.1  |        |      |        |        |                    |        | 1.1  |            |       |               |        |    |        | 4.5      |                |        |     |       |              |
| 30 | 1 e 5 | co i uma                 | es - ate (con-                | duit 15)       | rate             | kg/br                        | 2.2  |        |      |        |        |                    |        | 2.2  |            |       |               |        |    |        | 3.1      |                |        |     |       |              |
| 35 | Тар   | 00 CO                    | t i ons                       | - e -          | 12(10            |                              | 1.5  |        |      |        |        |                    |        | 1.5  |            |       |               |        |    |        | 0        |                |        |     |       |              |
| •  | Ì     | distillation             |                               | sure<br>1      |                  | top<br>kg/cm <sup>2</sup> -G | 6.5  |        |      |        |        |                    |        | 6.5  |            |       | •             |        |    |        | <b>~</b> |                |        |     |       |              |
| 40 |       |                          | Reaction<br>Tempe-P           | rature         | co l un          | of to                        | 203  |        |      |        |        |                    |        | 202  |            |       |               |        |    |        | 204      |                |        |     |       |              |
|    |       |                          | liquid<br>feeding             | Composit       | t ion            | *1%                          | 1    | I      |      |        |        |                    |        | 1    | <u> </u>   |       |               |        |    |        | DNC      | (200           |        |     |       |              |
| 45 |       |                          | Feed<br>From                  | 90 -           | rate             | kg/br                        | 1    |        |      |        |        |                    |        | 1    |            |       |               |        |    |        | 3.0      |                |        |     |       |              |
|    |       | t continuous             | liquid<br>feeding             | Composi-       | i on             | wt%                          | DMC  | (72.4) | PhoH | (26.5) | 2 S    | - 6- 4-<br>- 6- 4- | (0.38) | DINC | (68.5)     | PhoH  | (30.4)<br>NPC | (F)    | Sn | (0.37) | DIC      | (50.6)<br>PhOH | (45.3) | MPC | (3.3) | Pb<br>(0.37) |
| 50 |       | First                    | i ced                         |                | 13 (6            | kg/hr                        | 6.4  |        |      |        |        |                    |        | 9.9  |            |       |               |        |    |        | 4.6      |                |        |     |       |              |
| 55 |       |                          | liquid<br>feeding             | Combo c i-     | t ion            |                              | DMC  | (81.1) | PhoH | (17.0) | (20,0) | (65.9)             |        | DINC | (79.9)     | FOR S | (18.3)        | (0.91) |    |        | DIC.     | 3.8<br>P.0H    | (92.8) | 2   | (1.8) |              |
|    |       |                          |                               | 9 0            | rate             |                              | 2.7  |        |      |        |        |                    |        | 2.7  |            |       |               |        |    |        | 6.0      |                |        |     |       |              |
|    |       |                          | 1 9                           | <u>.</u>       |                  |                              | 22   |        |      |        |        |                    |        | 23   |            |       |               |        |    |        | 24       |                |        |     |       |              |

|    |       |                               |                                        |                                       | _                | _      |         | _      |            |                   |        |               |         |        |       |                                       | _    |        |        | _         |       |              |
|----|-------|-------------------------------|----------------------------------------|---------------------------------------|------------------|--------|---------|--------|------------|-------------------|--------|---------------|---------|--------|-------|---------------------------------------|------|--------|--------|-----------|-------|--------------|
| 5  |       |                               | na te                                  | Selec-<br>tivity                      | Type<br>Sype     | 250    | (88)    |        |            |                   |        | DPC           | (98)    |        |       |                                       | DPC  | (38)   |        |           |       |              |
| 5  |       |                               | Diaryl                                 | Amount<br>of                          | Type<br>7/kgHr   | DIC.   | (305)   |        |            |                   |        | DPC           | (\$0\$) |        |       |                                       | DPC  | (625)  |        |           |       |              |
| 10 |       |                               | Column bot-                            | duit28)<br>Composi-                   | . 3º             | DTC    | (30.3)  |        |            |                   |        | DPC           | (35.4)  |        |       |                                       | DPC  | (62.5) |        | •         |       |              |
|    |       | i-s tag                       |                                        | FlowComp                              | /8/              | 0.     |         |        |            |                   |        | 0.78          |         |        |       |                                       | 0.85 |        |        |           |       |              |
| 15 |       | continuous multi-stage        | onsCondens-                            | duit25)<br>Flow                       |                  | ص<br>ص |         |        |            |                   |        | 4.7           |         |        |       |                                       | 3.5  |        |        |           |       |              |
|    |       | t inuo                        |                                        | Re-<br>flux                           |                  | 1.8    |         |        |            |                   |        | 2.1           |         |        |       |                                       | 1.7  |        |        |           |       |              |
| 20 |       | Second con                    | P c c                                  | sure<br>at                            | top<br>BHR       | 200    |         |        |            |                   |        | 220           |         |        |       |                                       | 260  |        |        |           |       |              |
|    |       | Se                            | Reaction<br>Tempe-P                    | rature<br>at<br>column                | 1<br>2<br>2<br>3 | 196    |         |        |            |                   |        | 198           |         |        |       |                                       | 199  |        |        |           |       |              |
| 25 | (2)   |                               | ~ B                                    | conduit 19)<br>lowComposi-<br>atekion | %1 <u>*</u>      | !      | (30.8)  |        | _• .       |                   |        | EPC           | (53.1)  |        |       |                                       | MPC  | (24.1) |        |           |       |              |
|    |       |                               | Column<br>ton                          | <u> </u>                              | k8/              | ₩.     |         |        |            |                   |        | 5.4           |         |        |       |                                       | 7.   |        |        |           |       |              |
| 30 | 1 e 5 | l uma                         | tionsCondens-Column<br>ate (con-tom li | duit 16)<br>Flow<br>rate              | kg/br            | 3.3    |         |        |            |                   |        | 2.9           |         |        |       |                                       | 3.2  |        |        |           |       |              |
|    | Tab   | 00 00                         | tions                                  | Ke-<br>flux<br>ratio                  |                  | 0      |         |        |            |                   |        | 0             |         |        |       |                                       | 0    |        |        |           |       |              |
| 35 |       | lti-stage distillation column | Reaction condi                         | sure<br>at<br>column                  | 10P              | و      |         | ٠      |            |                   |        | -             |         |        |       |                                       | 9    |        |        |           | ,     |              |
| 40 |       | age di                        | React i                                | 72146<br>21<br>00 1480                | <u>နီ</u> ပ      | 204    |         |        |            |                   |        | 202           |         |        |       |                                       | 203  |        |        |           |       |              |
|    |       | Bulti-st                      | liquid<br>feeding                      | Composi-<br>tion                      |                  | ,      | (199)   |        |            |                   |        | DEC<br>(a) a) | PhoH    | (3.1)  |       |                                       | DIKC | (90.5) | (3.5)  |           |       |              |
| 45 | ŀ     | nons                          |                                        | rate                                  | kg/br            | 2.3    |         |        |            |                   |        | 3.0           |         |        |       |                                       | 3.1  |        |        |           |       |              |
|    |       | =                             | liquid<br>feeding                      | Composi-<br>tion                      |                  | DINC   | COH (2) | (42.5) | ortic<br>S | (6.5)<br><b>2</b> | (0.32) | DEC           | PhoH    | (30.0) | 3.0   | Pb<br>(0.32)                          | DMC  | (50.4) | (46.1) | MPC       | (3.1) | Sn<br>(0.38) |
| 50 |       | Firs                          | P 8                                    | -                                     | kg/br            | 8.8    |         |        |            |                   |        | 5.3           |         |        | ,     |                                       | 4.5  |        |        | - 15-2-11 |       |              |
|    |       |                               | liquid<br>feeding                      | Composi-Flow                          | wtS              | DIAC   | S . E   | (61.4) | Pb         | (4.34)            |        | DEC<br>(10 8) | PhoH    | (84.4) | (2.6) | · · · · · · · · · · · · · · · · · · · |      | (26.4) | (71.5) | Sa        | (2.0) |              |
| 55 |       |                               | 0 0 0                                  | 100                                   | 18/br            | 2.0    |         |        |            |                   |        | 0.68          |         |        |       |                                       | 0.95 |        |        |           |       |              |
|    |       |                               | N B                                    | v<br>-                                |                  | 52     |         |        | ·          |                   |        | 92            |         |        |       |                                       | 27   |        |        |           |       |              |
|    |       |                               |                                        |                                       |                  |        |         |        |            |                   |        |               |         |        |       |                                       |      |        |        |           |       |              |

(3)

.

|                                                      | _         |           | ,          | _          | _        |                                         | <del></del>      |        |      |        | _   | _     |    |        | _            |        |      |        |     | _     |
|------------------------------------------------------|-----------|-----------|------------|------------|----------|-----------------------------------------|------------------|--------|------|--------|-----|-------|----|--------|--------------|--------|------|--------|-----|-------|
|                                                      | _         | nate      | Se lec-    | t i y i t  |          | Type                                    | )<br>2<br>2<br>2 | (36)   | ;    |        |     |       |    |        | DPC          | (38)   |      |        |     |       |
|                                                      | Diary     | carbo     | Amount     | Jo         | Product  | Type                                    | DPC              | (143)  | ;    |        |     |       |    |        | DPC          | (662)  |      |        |     |       |
| ə                                                    | a bot-    | iquid     | lu i t 28) | -isogmo.   | 100      | 8                                       | 3.6 D. 79 DPC    | (74.3) | ;    |        |     |       |    |        | DPC          | (66.2) |      |        |     |       |
| -5128                                                | 100<br>El | _<br>     | (cond      | Flow       | rale     | /s :                                    | 0.79             |        |      |        |     |       |    |        | 0.13         |        |      |        |     |       |
| is multi-                                            | oudens-   | te (con-  | luit 25)   | Flow       | 1116     | 10/80                                   | 3.6              |        |      |        |     |       |    |        | 1.0 0.13 DPC |        |      |        | •   |       |
| inuou                                                | ions      |           | ا<br>ا     | lux        | 2 t i o  |                                         | 1.5              |        |      |        |     |       |    |        | 1:0          |        |      | _      |     |       |
| Second continuous multi-stage<br>distillation column | n condit  | Pres-     | sure       | ~          | colomn t | top                                     | 560              | -      | _    |        |     |       | ,- |        | 260          |        |      |        |     |       |
| Sec                                                  | Reactio   | Тепре-    | rature     | <u>.</u>   | co lunu  | 100 E 00                                | 197              |        |      |        |     |       |    |        | 198          |        |      |        |     |       |
|                                                      | -) oq uu  | l iquid   | duit [9)   | Compos i-  | 1 00     | *                                       | MPC              | (26.9) |      |        | •_  |       |    |        | MPC          | (18.1) |      |        |     |       |
|                                                      | Co lu     | 8         | 5          | F 104      | rate     | 78.                                     | -                |        |      |        |     |       |    |        | =            |        |      |        |     | _     |
| luma                                                 | _saapaoj  | ale (con- | dui(16)    | F 0 W      | rate     | 18/1/6                                  | 3.4              |        |      |        |     |       |    |        | 0.75         |        |      |        |     |       |
| 00 0                                                 | ions      |           | ٥          | lux        | at 10    |                                         | 0                |        |      |        |     |       |    |        | 0            |        |      |        |     |       |
| ti-stage distillation column                         | on condit | Pres-     | Suce       | =          | calumn   | 10p                                     | 9                |        |      |        |     |       |    |        | 9            |        |      |        |     |       |
| age di:                                              | Reactio   | fempe-    | rature     |            | co l uno | 1<br>1<br>1<br>1<br>1                   | 204              |        |      |        |     |       |    |        | 203          |        |      |        |     |       |
| malti-st                                             | liquid    | feeding   | 200        | Compos i-  | l ion    | ¥18                                     | DMC              | (91.3) | PhoH | (8.7)  |     |       |    |        |              | (30.3) | PhoH | (9.1)  |     |       |
| snon                                                 | paag      | E com     | 9          | F 104      | r 1 t e  | kg/hr                                   | 3.2              |        |      |        |     |       |    |        | 0.78         |        |      |        |     |       |
| First continuous mul                                 | pinbil    | feeding   | 9          | Composi-   | tion     | 818                                     | DMC              | (49.3) | PhoH | (44.8) | MPC | (2.3) | ij | (0.40) |              | (51.3) | PhoH | (45.6) | KPC | (0,0) |
| Firş                                                 | Feed      | 80.<br>   |            | Flow       | rale     | ke/hr                                   | 4.6              | -      |      |        |     |       |    |        | =            |        |      |        |     |       |
|                                                      | hiquid    | leeding   | 2          | Compos i - | ale lion | Type Type Type Type Type Type Type Type | OMC              | (31.5) | PhoH | (65.2) |     | (1.9) |    |        | OMC          | (41.8) | PboH | (58.2) |     |       |
|                                                      | Feed      | 8         | 911        | - no.      | rale     | kg/br                                   | 0.99             |        |      |        |     |       |    |        | 0.11         |        |      |        |     |       |
|                                                      | 1         | <u>.</u>  | <u>۔</u>   |            |          |                                         | 82               |        |      |        |     |       |    |        | 30           |        |      |        |     | _     |
|                                                      |           |           |            |            |          |                                         |                  |        | 27   | ,      |     | _     |    |        |              |        |      |        |     |       |

|     | 50         |         | 45                                        | 40                                                                                                                                                           | 35                      | 30                       | 25                                                  | 20                     | 15                     | 10                      | 5     |
|-----|------------|---------|-------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------|-----------------------------------------------------|------------------------|------------------------|-------------------------|-------|
| (De | scripti    | 0.0     | (Description of symbols)                  |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | DMC        | ••      | dimethyl ca                               | carbonate                                                                                                                                                    |                         |                          |                                                     |                        |                        |                         |       |
|     | PhoH       | ••      | phenol                                    |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | P b        | ••      | lead                                      |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | MPC        | ••      | methyl phen                               | henyl carbonate                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | DPC        | ••      | diphenyl ca                               | carbonate                                                                                                                                                    |                         |                          |                                                     |                        |                        |                         |       |
|     | СОН        | ••      | p-cresol                                  |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | MTC        | ••      | methyl toly                               | olyl carbonate                                                                                                                                               |                         |                          |                                                     |                        |                        |                         |       |
|     | DTC        | ••      | ditolyl car                               | carbonate                                                                                                                                                    |                         |                          |                                                     |                        |                        |                         |       |
|     | DEC        | ••      | diethyl car                               | carbonate                                                                                                                                                    |                         |                          |                                                     |                        |                        |                         |       |
|     | EPC        | ••      | ethyl phenyl carbonate                    | l carbonate                                                                                                                                                  |                         |                          |                                                     |                        |                        |                         |       |
|     | Sn         | ••      | t in                                      |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | Ţ          | ••      | titanium                                  |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | w 1 %      | ••      | % by weight                               |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
| (N  | (No 1 e)   |         |                                           |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     | 1. Th      | 9       | 1. The catalyst conc                      | oncentration was determined by means of an ICP (inductively coupled plasm                                                                                    | determin                | ned by mean              | of an I(                                            | P (induct              | ively coup             | ied plasm               | æ     |
|     | еп         | n i s s | emission spectral                         | ral analyter).                                                                                                                                               | The catal               | lyst concer              | The catalyst concentration is expressed in terms of | expresse               | d in terms             | of the                  |       |
|     | 00         | ) D C ( | concentration (%                          | (% by weight) of a catalyst element in the liquid.                                                                                                           | f a cataly              | rst elemen               | t in the t                                          | quid.                  |                        |                         |       |
|     | 2. Th      | je ,    | The amount of pro                         | produced diaryl carbonate is expressed in terms of grams of the product                                                                                      | carbonate               | e is expre               | ssed in ter                                         | rms of gra             | ms of the              |                         | per   |
|     | , <u>M</u> | 0       | the column                                | kg of the column bottom liquid (conduit 28) and per hour.                                                                                                    | d (conduit              | 1 28) and                | per hour.                                           |                        |                        |                         |       |
|     | 3. Th      | e :     | 3. The selectivity o<br>Selectivity of th | ty of the diaryl carbonate is calculated by means of the following formula.<br>f the diaryl carbonate (%) = [selectivity (%) at Step 1 based on the aromatic | carbonate<br>bonate (%) | e is calcu<br>) = [selec | lated by motivity (%)                               | eans of that at Step 1 | e followin<br>based on | ng formula<br>the aroma | 1 i c |
|     | by         | dre     | xy compound                               | hydroxy compound converted] $	imes$ [selectivity (%) at Step 2 besed on the alkyl aryl carbonate                                                             | . [select               | ivity (%)                | at Step 2                                           | besed on t             | he alkyl a             | aryl carbo              | nate  |
|     | 9 0        | ) D V ( | converted] ÷ 100                          |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |
|     |            |         |                                           |                                                                                                                                                              |                         |                          |                                                     |                        |                        |                         |       |

| 5  |        |
|----|--------|
| 10 |        |
| 15 |        |
| 20 |        |
| 25 | 9<br>9 |
| 30 | Tab 1  |
| 35 |        |
| 40 |        |
| 45 |        |

|              | F              | irst cont | First continuous multi-stage distillation column                       | i-stage d | istillation                     | column     |          |                                                                                       |
|--------------|----------------|-----------|------------------------------------------------------------------------|-----------|---------------------------------|------------|----------|---------------------------------------------------------------------------------------|
| Feeding p    | pipe 2         | Cond      | Conduit 6                                                              | Feeding   | Feeding pipe 8' Conduit 16      | Conduit 16 |          | Conduit 19                                                                            |
| Flow rate Co | Composition    | Flow rate | Composition                                                            | Flow rate | Composition                     | Flow rate  | low rate | mposition Flow rate Composition Flow rate Composition Flow rate Flow rate Composition |
| (kg/Hr)      | Type (wt%)     | (kg/Hr)   | ype(w1%) (kg/Hr) Type(w1%) (kg/Hr) Type(w1%) (kg/Hr) (kg/Hr) Type(w1%) | (kg/Hr)   | Type (wt%)                      | (kg/Hr)    | (kg/Hr)  | Type (wt%)                                                                            |
| 5.0          | DMC(13.1) 24.5 | 24.5      | DMC (51.2)                                                             | 41.5      | DMC (51.2) 41.5 DMC (89.5) 42.4 | 42.4       | 23.6     | MPC (28.9)                                                                            |
|              | PhOH(86.9)     |           | PhOH(43.3)                                                             |           | PhOH(10.5)                      |            |          |                                                                                       |
|              |                | •         | MPC (4.7)                                                              |           |                                 |            |          |                                                                                       |
|              |                |           | Pb (0.42)                                                              |           |                                 |            |          |                                                                                       |

| e v s | First evaporator So  | Second co | ntinuous m | ulti-stage                       | distillat | econd continuous multi-stage distillation column                              |          | Second evaporator | 0 f        |
|-------|----------------------|-----------|------------|----------------------------------|-----------|-------------------------------------------------------------------------------|----------|-------------------|------------|
| 2     | onduit 40 Conduit 38 |           | uit 41     | Conduit 41 Conduit 25 Conduit 32 | Conde     | 11 32                                                                         | Cond     | Conduit 50        | Conduit 47 |
| 22    | Flow rateFlow rateF  | Flow rate | Compositio | nFlow rate                       | Flow rate | low rateCompositionFlow rateFlow rateCompositionFlow rateCompositionFlow rate | low rate | Composition       | Flow rate  |
|       | (kg/Hr) (kg/Hr)      | (kg/Hr)   | Type (wt%) | (kg/Hr)                          | (kg/Hr)   | (kg/Hr) Type(wt%) (kg/Hr) (kg/Hr) Type(wt%) (kg/Hr) Type(wt%) (kg/Hr)         | (kg/Hr)  | Type (wt%)        | (kg/Hr)    |
|       | 1.3                  | 23.3      | DMC (43.1  | DMC (43.1) 18.3 5.3              |           | DPC(95.4) 4.0                                                                 | 4.0      | DPC (98.3)        | 1.2        |
|       |                      |           | PbOH(24.5) | _                                |           |                                                                               |          |                   |            |
|       | -                    |           | MPC (27.1) | _                                |           |                                                                               |          |                   |            |
|       |                      |           | DPC (4.5)  |                                  |           |                                                                               |          |                   |            |
|       |                      |           | Pb (0.8)   |                                  |           |                                                                               |          |                   |            |

| 5          |  |                        |           |        |      |                         |           |          |        | he liquid                                                                   |                                                                           |
|------------|--|------------------------|-----------|--------|------|-------------------------|-----------|----------|--------|-----------------------------------------------------------------------------|---------------------------------------------------------------------------|
| 10         |  |                        |           |        |      |                         |           |          |        | entration is expressed in terms of the Pb concentration (wt%) in the liquid | analyzer).                                                                |
| 15         |  |                        |           |        |      |                         |           |          |        | ntration                                                                    | tral anal                                                                 |
| 20         |  |                        |           |        |      |                         |           |          |        | e Pb conce                                                                  | ssion spec                                                                |
| 25         |  |                        |           |        |      |                         |           |          |        | rms of th                                                                   | lasma emi                                                                 |
| 30         |  |                        |           |        |      |                         |           |          |        | ssed in te                                                                  | coupled p                                                                 |
| 35         |  |                        | ð         |        |      | bonate                  | Ð         |          |        | is expres                                                                   | ductively                                                                 |
| 40         |  | <b>( s )</b>           | carbonate |        |      | methyl phenyl carbonate | carbonate | ght      |        | entration                                                                   | n ICP (in                                                                 |
| <b>4</b> 5 |  | of symbol              | dimethyl  | phenol | lead | methylp                 | diphenyl  | % by wei |        | The catalyst conc                                                           | neans of a                                                                |
| 50         |  | (Description of symbol | : DMC     | PhOH:  | . d4 | MPC :                   | DPC :     | * t %    | (Note) | The cata                                                                    | measured by means of an ICP (inductively coupled plasma emission spectral |
| 55         |  | ě                      |           |        |      |                         |           |          | Š      |                                                                             | E 9                                                                       |

EP 0 461 274 B1

ø

| First conti         | First continuous multi-stage | -stage | Second continuous multi-stage | inuous mult         | i-stage | Reaction results | results     |
|---------------------|------------------------------|--------|-------------------------------|---------------------|---------|------------------|-------------|
| distillation column | n column                     |        | distillation column           | n column            |         |                  |             |
| Reactio             | Reaction conditions          | S      | Reactio                       | Reaction conditions | 8       | Diaryl carbonate | rbonate     |
| Temperature         | Pressure                     | Reflux | Temperature Pressure          | Pressure            | Reflux  | Amount of        | Selectivity |
| at column           | at column                    | ratio  | at column                     | at column           | ratio   | product          |             |
| bottom              | top                          |        | bottom                        | top                 |         | Type             | Type        |
| (၃)                 | (kg/cm²-G)                   |        | (၃)                           | (mmHg)              |         | (g/kg·Hr)        | (%)         |
| 203                 | 6.5                          | 0      | 198                           | 280                 | 1.5     | DPC              | DPC         |
|                     |                              |        |                               |                     |         | (883)            | (86)        |
|                     |                              |        |                               |                     |         |                  |             |
|                     |                              | _      | _                             |                     |         |                  |             |

Selectivity of the diaryl carbonate (%) = [selectivity (%) at Step 1 based on the aromatic The amount of the produced diaryl carbonate is expressed in terms of grams of the product The selectivity of the diaryl carbonate is calculated by means of the following formula. [selectivity (%) at Step 2 based on the alkyl aryl carbonate 5 10 15 20 per kg of withdrawn liquid from conduit 50 and per hour. 25 30 35 diphenyl carbonate hydroxy compound converted] X 40 (Description of symbols) by weight ÷ 100 45 converted] DPC w t % 50 55

Example 31

Using a distillation column as shown in Fig.2 as the first continuous multi-stage distillation column, a mix-

ture of dim thyl carb nate, para-cresol and Pb(OPh)<sub>2</sub> [46 % by weight of dim thyl carbonate, 54 % by weight of para-cresol, and 10 mmol/kg of Pb(OPh)<sub>2</sub>] was continuously fed at 7.0 kg/hr from f eding pip 2 through preheater 5, and simultaneously, dim thyl carbonat was continuously f d at 2.8 kg/hr from feeding pipe 8' through evaporator 10' and conduit 11, thereby ffecting reaction at a t mp rature at column bottom of 205 °C and at a pressure at column top of 6 kg/cm<sup>2</sup>-G, while continuously withdrawing as a condensate a gas component containing methanol at 5.0 kg/hr from column top 17 through conduit 12 and condenser 13, and on the other hand, continuously withdrawing a column bottom liquid containing 30 % by weight of methyl tolyl carbonate at 4.8 kg/hr from the column bottom through conduit 19.

Substantially the same operation was performed using diethyl carbonate, phenol and Pb(OPh)<sub>2</sub>, to thereby obtain a column bottom liquid containing 28.8 % weight of ethyl phenyl carbonate.

A distillation column as shown in Fig. 1 was used as the second continuous multi-stage distillation column, and the column bottom liquid from the first continuous multi-stage distillation column was continuously fed to the second continuous multi-stage distillation column at 4.8 kg/hr from feeding pipe 2 through preheater 5 and conduit 6. Simultaneously, the above-mentioned column bottom liquid containing ethyl phenyl carbonate was continuously fed at 5.0 kg/hr from the same feeding pipe 2. The temperature at the bottom of the second continuous multi-stage distillation column was 200 °C, and the pressure at column top 17 was 26 kPa (200 mmHg). A gas component containing dimethyl carbonate, diethyl carbonate and methyl ethyl carbonate was continuously withdrawn as a condensate at 7.7 kg/hr from column top 17 through conduit 12, condenser 13 and conduits 14 and 16. On the other hand, the column bottom liquid was continuously withdrawn at 2.1 kg/hr through conduits 8 and 19. 88 % by weight of the column bottom liquid was diaryl carbonate comprising diphenyl carbonate, ditolyl carbonate and phenyl tolyl carbonate, and the proportions of diphenyl carbonate:ditolyl carbonate were about 1:1:0.8.

# Example 32

10

25

35

45

50

By substantially the same operation as that employed with the first continuous multi-stage distillation column in Example 25, a column bottom liquid containing methyl tolyl carbonate was continuously withdrawn at 4.8 kg/hr from dimethyl carbonate and para-cresol, and the withdrawn liquid was continuously fed to the second continuous multi-stage distillation column while methyl phenyl carbonate was continuously fed to the second continuous multi-stage distillation column at 1.36 kg/hr through conduit 19. The reaction conditions in the second continuous multi-stage column were substantially the same as those of Example 25. From the time when methyl phenyl carbonate was added, the amount of dimethyl carbonate in the feed liquid fed from feeding pipe 2 was gradually decreased so as to obtain a rate of 0.38 kg/hr. Instead, the amount of dimethyl carbonate in the feed liquid from conduit 6 was increased by 0.36 kg/hr. The increase was due to the fact that the reaction in the second continuous multi-stage distillation column, in which transesterification occurred between methyl tolyl carbonate and methyl phenyl carbonate, caused an increase in the amount of the dimethyl carbonate formed as a low boiling point by-product.

On the other hand, the column bottom liquid containing 90 % by weight of diaryl carbonate comprised of diphenyl carbonate, ditolyl carbonate and phenyl tolyl carbonate was continuously withdrawn at 2 kg/hr from the bottom of the second continuous multi-stage distillation column. The proportions in the diaryl carbonate of diphenyl carbonate:ditolyl carbonate:phenyl tolyl carbonate were about 1:1:0.75.

# Brief Description of the Drawings

Fig. 1, Fig. 2, Fig. 3, Fig. 4 and Fig. 5 are diagrams showing various modes of processes for practicing the process of the present invention; and

Fig. 6 is a diagram of a reactor apparatus for use in the conventional process described in Comparative Examples 1, 2 and 3.

# Industrial Applicability

The process of the present invention in which a continuous multi-stage distillation column is used to continuously produce an aromatic carbonat at a high reaction rat, with a high silectivity and in a high yield, can be advantagiously utilized in the mass production of an aromatic carbonate, which is useful as a material for the production of aromatic polycarbonates, whos utility as engine ring plastics is increasing in recent years, without using poisonous phosgene or as a material for the production of various isocyanates without using poisonous phosgene.

# Claim

 A proc ss for producing an aromatic carbonat which comprises transes sterifying a starting material selected from the group consisting of a dialkyl carbonat represented by

10

5

an alkyl aryl carbonate represented by

15

and a mixture thereof with a reactant selected from the group consisting of an aromatic hydroxy compound represented by Ar<sup>1</sup>OH, an alkyl aryl carbonate represented by

25

20

and a mixture thereof, wherein each of R<sup>1</sup>, R<sup>2</sup> and R<sup>3</sup> independently represents an alkyl group having 1 to 10 carbon atoms, an alicyclic group having 3 to 10 carbon atoms or an aralkyl group having 6 to 10 carbon atoms and each of Ar<sup>1</sup>, Ar<sup>2</sup> and Ar<sup>3</sup> independently represents an aromatic group having 5 to 30 carbon atoms, to thereby produce an aromatic carbonate or aromatic carbonate mixture corresponding to the starting material and the reactant and represented by

35

30

and/or

40

45

wherein R and Ar are, respectively, selected from R¹, R² and R³ and selected from Ar¹, Ar² and Ar³ in correspondence to the starting material and the reactant and produce an aliphatic alcohol, a dialkyl carbonate or a mixture thereof corresponding to the starting material and the reactant and represented by ROH and/or

50



55

wh r in R is as defin d above, as a by-product, charact rized in that said starting mat rial and said reactant are continuously fed t a continuous multi-stag distillation column to eff ct a liquid phase and/or
gas-liquid phase transesterification r action therebetween in the presence of a catalyst in said distillation
column, while continuously withdrawing a high boiling point r action mixtur containing th produced aromatic carbonat or aromatic carbonat mixture in a liquid form from a lower portion of th distillation

5

10

15

20

25

30

35

40

45

50

55

column and continuously withdrawing a low boiling point reaction mixture containing the by-product in a gaseous form from an upper portion of the distillation column by distillation, thereby an nabling the aromatic carbonate or aromatic carbonate mixture to be produced continuously.

- 2. The process according to claim 1, characterized in that said catalyst is a catalyst which is soluble in said liquid phase, and is present in a state dissolved in said liquid phase within the continuous multi-stage distillation column, and/or that said catalyst is a solid catalyst which is substantially insoluble in said liquid phase, and is disposed, in a state undissolved in said liquid phase, within the continuous multi-stage distillation column.
- 3. The process according to claim 1, characterized in that said continuous multi-stage distillation column is used as a first continuous multi-stage distillation column and has a second continuous multi-stage distillation column connected thereto and that the starting material and the reactant which are continuously fed to the first continuous multi-stage distillation column are, respectively, a dialkyl carbonate represented by

and an aromatic hydroxy compound represented by Ar¹OH, the aromatic carbonate or aromatic carbonate mixture contained in the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column is an alkyl aryl carbonate represented by

in which R¹ and Ar¹ are as defined above, and the by-product contained in the produced low boiling point reaction mixture continuously withdrawn from the upper portion of the first distillation column is an aliphatic alcohol represented by R¹OH, and which process further comprises continuously feeding the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column and containing the alkyl aryl carbonate represented by

in which R1 and Ar1 are as defined above, and an alkyl aryl carbonate reactant represented by

in which R<sup>3</sup> is the same as or different from R<sup>1</sup> and Ar<sup>3</sup> is the same as or different from Ar<sup>1</sup> with the proviso that R<sup>3</sup> and Ar<sup>3</sup> are, respectively, not simultaneously the same as R<sup>1</sup> and Ar<sup>1</sup>, to the second continuous multi-stage distillation column to effect a liquid phase and/or gas-liquid phase transesterification reaction therebetween in the presence of a catalyst in said second distillation column, thereby producing a high boiling point reaction mixture containing a diaryl carbonate or diaryl carbonate mixture represented by

in which Ar¹ and Ar³ are as d fined above, and a low boiling point reaction mixture containing a dialkyl carbonat by-product r pr sent d by

R<sup>1</sup>OCOR<sup>3</sup>, R<sup>1</sup>OCOR<sup>3</sup>

10 and/or

5

15

20

25

30

35

40

45

50

55

in which  $R^1$  and  $R^3$  are as defined above, wherein the produced high boiling point reaction mixture is continuously withdrawn in a liquid form from a lower portion of said second distillation column and the low boiling point reaction mixture is continuously withdrawn in a gaseous form from an upper portion of said second distillation column by distillation.

- 4. The process according to claim 3, characterized in that said catalyst is a catalyst which is soluble in said liquid phase, and is present in a state dissolved in said liquid phase within at least one of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column, and/or that said catalyst is a solid catalyst which is substantially insoluble in said liquid phase, and is disposed, in a state undissolved in said liquid phase, within at least one of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column.
- 5. The process according to claim 3 or 4, characterized in that R³ is the same as R¹ and Ar³ is different from Ar¹, and which process further comprises recycling the low boiling point reaction mixture withdrawn from the upper portion of the second continuous multi-stage distillation column and containing a dialkyl carbonate represented by

to the first continuous multi-stage distillation column.

6. The process according to claim 1, characterized in that said continuous multi-stage distillation column is used as a first continuous multi-stage distillation column and has a second continuous multi-stage distillation column connected thereto and that the starting material and the reactant which are continuously fed to the first continuous multi-stage distillation column are, respectively, a dialkyl carbonate represented by

and an aromatic hydroxy compound represented by Ar¹OH, the aromatic carbonate or aromatic carbonate mixture contained in the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column is an alkyl aryl carbonate represented by

R<sup>1</sup>OCOAr<sup>1</sup>

5

10

15

20

25

30

35

40

45

50

55

in which R¹ and Ar¹ are as defined above, and the by-product contained in the produced low boiling point reaction mixture continuously withdrawn from the upper portion of the first distillation column is an aliphatic alcohol represented by R¹OH, and which process further comprises continuously feeding the produced high boiling point reaction mixture continuously withdrawn from the lower portion of the first distillation column and containing the alkyl aryl carbonate represented by

R<sup>1</sup>OCOAr<sup>1</sup>,

in which R¹ and Ar¹ are as defined above, to the second continuous multi-stage distillation column to effect a liquid phase and/or gas-liquid phase, same species-intermolecular transesterification reaction between molecules of the alkyl aryl carbonate in the presence of a catalyst in said second distillation column, thereby producing a high boiling point reaction mixture containing a diaryl carbonate represented by

Ar<sup>1</sup>OCOAr<sup>1</sup>,

in which Ar¹ is as defined above, and a low boiling point reaction mixture containing a dialkyl carbonate by-product represented by

R<sup>1</sup>OCOR<sup>1</sup>,

in which R¹ is as defined above, wherein the produced high boiling point reaction mixture is continuously withdrawn in a liquid form from a lower portion of said second continuous multi-stage distillation column and the low boiling point reaction mixture is continuously withdrawn in a gaseous form from an upper portion of said second continuous multi-stage distillation column.

7. The process according to claim 6, characterized in that the process further comprises recycling the low boiling point reaction mixture withdrawn from the upper portion of said second continuous multi-stage distillation column and containing the dialkyl carbonate represented by

> R<sup>1</sup>OCOR<sup>1</sup> | O

to said first continuous multi-stage distillation column.

8. The process according to claim 6 or 7, characterized in that said catalyst is a catalyst which is soluble in said liquid phase, and is present in a state dissolved in said liquid phase within at least one of the first continuous multi-stag distillation column and the second continuous multi-stage distillation column, and/or that said catalyst is a solid catalyst which is substantially insoluble in said liquid phase, and is disposed, in a state undissolved in said liquid phase, within at I ast one of the first continuous multi-stage distillation column.

5

10

15

25

30

40

45

50

- 9. Th process according to claim 8, characterized in that said catalyst is a catalyst which is s lubl in said liquid phas, and is present in a state dissolved in said liquid phase within each of the first continuous multi-stage distillation column and the second continuous multi-stage distillation column, wherein the respective catalysts used in the first and second distillation columns are the same or different.
- 10. The process according to claim 6 or 7, characterized in that part or all of the catalyst used in the first continuous multi-stage distillation column is present in a state dissolved in said liquid phase and that, in feeding to the second continuous multi-stage distillation column the high boiling point reaction mixture withdrawn in liquid form from the lower portion of the first distillation column, the withdrawn high boiling point reaction mixture in liquid form is introduced to a first evaporator to effect a separation of said reaction mixture into an evaporated component containing the alkyl aryl carbonate represented by

- and a residual liquid having the catalyst dissolved therein, and part or all of said evaporated component is fed to the second continuous multi-stage distillation column, while recycling part or all of the residual liquid containing the dissolved catalyst to the first continuous multi-stage distillation column.
  - 11. The process according to claim 6 or 7, characterized in that part or all of the catalyst used in the second continuous multi-stage distillation column is present in a state dissolved in said liquid phase, and that the process further comprises introducing the high boiling point reaction mixture withdrawn in liquid form from the lower portion of the second distillation column to a second evaporator to effect a separation of said reaction mixture into an evaporated component containing a diaryl carbonate represented by

- and a residual liquid having said catalyst dissolved therein, and recycling part or all of the residual liquid containing the dissolved catalyst to the second continuous multi-stage distillation column.
  - 12. The process according to claim 10, characterized in that part or all of the catalyst used in the second continuous multi-stage distillation column is present in a state dissolved in said liquid phase, and that the process further comprises introducing the high boiling point reaction mixture withdrawn in liquid form from the lower portion of the second distillation column to a second evaporator to effect a separation of said reaction mixture into an evaporated component containing a diaryl carbonate represented by

- and a residual liquid having said catalyst dissolved therein, and recycling part or all of the residual liquid containing the dissolved catalyst to the second continuous multi-stage distillation column.
- 13. The process according to claim 1 or 2, characterized in that said catalyst is selected from the group consisting of a lead compound, a copper family metal compound, an alkali metal complex, a zinc complex, a cadmium complex, an iron family metal compound, a zirconium complex, a Lewis acid or Lewis acid-forming compound, an organotin compound and an inorganic oxide.
- 14. The process according to any one of claims 3 to 12, characterized in that said catalyst is selected from the group consisting of a lead compound, a copper family metal compound, an alkali metal complex, a zinc complex, a cadmium complex, an iron family metal compound, a zirconium complex, a Lewis acid or

L wis acid-f rming compound, an organotin compound and an in rganic oxid .

- 15. The pr cess according to claim 1, 2 or 13, charact rized in that said continuous multi-stag distillation column is of a plate column type, a packed column type or a mixed type of plate column and packed column.
  - 16. The process according to any one of claims 3 to 14, characterized in that each of said first continuous multi-stage distillation column and said second continuous multi-stage distillation column is, independently, of a plate column type, a packed column type or a mixed type of plate column and packed column.

# Patentansprüche

10

15

20

30

40

 Verfahren zur Herstellung eines aromatischen Carbonats, umfassend die Umesterung eines aus der Gruppe der Dialkylcarbonate, dargestellt durch

Alkylarylcarbonate, dargestellt durch

und Gemischen davon ausgewählten Ausgangsmaterials mit einem Reaktanten, der aus der Gruppe der aromatischen Hydroxyverbindungen, dargestellt durch Ar¹OH, der Alkylarylcarbonate, dargestellt durch

und Gemischen davon ausgewählt ist, wobei jedes von R¹, R² und R³ unabhängig für eine Alkylgruppe mit 1 bis 10 Kohlenstoffatomen, eine alicyclische Gruppe mit 3 bis 10 Kohlenstoffatomen oder eine Aralkylgruppe mit 6 bis 10 Kohlenstoffatomen steht und jedes von Ar¹, Ar² und Ar³ unabhängig eine aromatische Gruppe mit 5 bis 30 Kohlenstoffatomen bedeutet, wobei, entsprechend dem Ausgangsmaterial und dem Reaktanten, ein aromatisches Carbonat oder ein Gemisch aromatischer Carbonate gebildet wird, dargestellt durch

wobei R und Ar jeweils unter R¹, R² und R³, bzw. unter Ar¹, Ar² und Ar³, entsprechend dem Ausgangsmaterial und dem Reaktanten, gewählt sind, und wobei als Nebenprodukt ein aliphatischer Alkohol, ein Dialkylcarbonat oder ein Gemisch davon gebildet wird, entsprechend dem Ausgangsmaterial und dem Reaktanten und die durch ROH und/oder

dargestellt sind, wob i R wie ob n d finiert ist, dadurch gekennzeichnet, daß das Ausgangsmaterial und der R aktant kontinuierlich in eine kontinuierliche Mehrstufen-Destillationskolonn ing leitet w rden, s daß zwischen diesen in Gegenwart ein s Katalysators in dieser Destillationskolonn eine Flüssigphas n- und/oder Gas-Flüssigphasen-Um st rungsr aktion stattfind t, währ nd ein Reaktionsgemisch mit hohem Siedepunkt, das das gebildete aromatische Carbonat oder Gemisch von aromatischen Carbonaten enthält, kontinuierlich in flüssiger Form aus dem unteren Teil der Destillationskolonne abgezogen wird und ein Reaktionsgemisch mit niederem Siedepunkt, das das Nebenprodukt enthält, in Gasform aus dem oberen Teil der Destillationskolonne durch Destillation abgezogen wird, wodurch die kontinuierliche Herstellung des aromatischen Carbonats oder des Gemisches von aromatischen Carbonaten ermöglicht wird.

- 2. Verfahren nach Anspruch 1, dadurch gekennzeichnet, daß der Katalysator ein in der flüssigen Phase löslicher Katalysator ist und im gelösten Zustand in der flüssigen Phase innerhalb der kontinuierlichen Mehrstufen-Destillationskolonne vorliegt und/oder daß der Katalysator ein fester Katalysator ist, der in dieser flüssigen Phase im wesentlichen unlöslich ist und innerhalb der kontinuierlichen Mehrstufen-Destillationskolonne in einem in der flüssigen Phase nicht gelösten Zustand vorliegt.
- 3. Verfahren nach Anspruch 1, dadurch gekennzeichnet, daß die kontinuierliche Mehrstufen-Destillationskolonne als eine erste kontinuierliche Mehrstufen-Destillationskolonne verwendet wird und daß mit ihr eine zweite kontinuierliche Mehrstufen-Destillationskolonne verbunden ist, und daß das Ausgangsmaterial und der Reaktant, die kontinuierlich in die erste Mehrstufen-Destillationskolonne eingeleitet werden, ein durch

5

10

15

20

30

40

45

50

dargestelltes, Dialkylcarbonat bzw. eine durch Ar¹OH dargestellte aromatische Hydroxyverbindung sind, wobei das aromatische Carbonat oder aromatische Carbonatgemisch, das in dem gebildeten Reaktionsgemisch mit hohem Siedepunkt, das kontinuierlich aus dem unteren Teil der ersten Destillationskolonne abgezogen wird, enthalten ist, ein durch

dargestelltes Alkylarylcarbonat ist, wobei R¹ und Ar¹ wie oben definiert sind, und daß das Nebenprodukt, das in dem gebildeten Reaktionsgemisch mit niederem Siedepunkt, das kontinuierlich aus dem oberen Teil der ersten Destillationskolonne abgezogen wird, enthalten ist, ein durch R¹OH dargestellter aliphatischer Alkohol ist, wobei das Verfahren außerdem die kontinuierliche Zuführung des gebildeten Reaktionsgemisches mit hohem Siedepunkt, das kontinuierlich aus dem unteren Teil der ersten Destillationskolonne abgezogen wird und das das Alkylarylcarbonat, dargestellt durch

wobei R1 und Ar wie oben definiert sind, und einen Alkylarylcarbonat-Reaktanten enthält, der durch

darg st llt ist, wob i R3 gleich wi oder verschied n von R1 ist und Ar3 gleich wi od r verschieden von

Ar¹ ist, mit der Maßgab, daß R³ und Ar³ nicht gleichz itig digliche B dutung wie R¹ und Ar¹ haben, in di zweite kontinuierliche M hrstufen-Destillationskolonn umfaßt, um eine Flüssigphasen- und/oder Gas-Flüssigphas n-Umesterungsreaktion zwischen diesen in Gegenwart eines Katalysators in dieser zweiten D stillationskolonne durchzuführen, wobei in R aktionsgemisch mit hoh m Siedepunkt, das in Diarylcarbonat oder Diarylcarbonat-Gemisch, dargestellt durch

5

10

20

25

30

35

45

55

wobei Ar<sup>1</sup> und Ar<sup>3</sup> wie oben definiert sind, enthält, und ein Reaktionsgemisch mit niederem Siedepunkt gebildet wird, welches ein Dialkylcarbonat-Nebenprodukt, dargestellt durch

wobei R¹ und R³ wie oben definiert sind, enthält, wobei das gebildete Reaktionsgemisch mit hohem Siedepunkt kontinuierlich in flüssiger Form aus dem unteren Teil der zweiten Destillationskolonne abgezogen wird und das Reaktionsgemisch mit niederem Siedepunkt kontinuierlich in Gasform aus dem oberen Teil der zweiten Destillationskolonne durch Destillation abgezogen wird.

- 4. Verfahren nach Anspruch 3, dadurch gekennzeichnet, daß der Katalysator ein in der flüssigen Phase löslicher Katalysator ist und in gelöstem Zustand in der flüssigen Phase innerhalb mindestens einer der ersten kontinuierlichen Mehrstufen-Destillationskolonne und der zweiten kontinuierlichen Mehrstufen-Destillationskolonne vorliegt und/oder daß der Katalysator ein fester Katalysator ist, der im wesentlichen unlöslich in der flüssigen Phase ist und in mindestens einer der ersten kontinuierlichen Mehrstufen-Destillationskolonne und der zweiten kontinuierlichen Mehrstufen-Destillationskolonne im in der flüssigen Phase nicht gelösten Zustand vorliegt.
- 5. Verfahren nach Anspruch 3 oder 4, dadurch gekennzeichnet, daß R³ und R¹ gleich sind und daß Ar³ verschieden von Ar¹ ist, und daß das Verfahren außerdem die Rückführung des Reaktionsgemisches mit niederem Siedepunkt, das aus dem oberen Teil der zweiten kontinuierlichen Mehrstufen-Destillationskolonne abgezogen wird und ein durch

- dargestelltes Dialkylcarbonat enthält, in die erste kontinuierliche Mehrstufen-Destillationskolonne umfaßt.
  - 6. Verfahren nach Anspruch 1, dadurch gekennzeichnet, daß die kontinuierliche Mehrstufen-Destillationskolonne als eine erste kontinuierliche Mehrstufen-Destillationskolonne verwendet wird und daß eine zweit kontinui rliche Mehrstuf n-Destillationskolonne mit ihr verbunden ist und das Ausgangsmaterial und der R aktant, die kontinuierlich in di erste kontinuierlich Mehrstuf n-Destillationskolonne ingeleitet werden, ein durch

5

10

dargestelltes Dialkylcarbonat bzw. eine durch Ar¹OH dargestellte aromatische Hydroxyverbindung sind, daß das aromatische Carbonat oder aromatische Carbonat-Gemisch, das in dem gebildeten Reaktionsgemisch mit hohem Siedepunkt vorliegt, welches kontinuierlich aus dem unteren Teil der ersten Destillationskolonne abgezogen wird, ein durch

R<sup>1</sup>OCOAr<sup>1</sup>

II

O

15

dargestelltes Arylcarbonat ist, wobei R¹ und Ar² wie oben definiert sind, und das Nebenprodukt, das in dem gebildeten Reaktionsgemisch mit niederem Siedepunkt vorliegt, das kontinuierlich aus dem oberen Teil der ersten Destillationskolonne abgezogen wird, ein durch R¹OH dargestellter aliphatischer Alkohol ist, wobei das Verfahren außerdem das kontinuierliche Einführen des gebildeten Reaktionsgemisches mit hohem Siedepunkt, das kontinuierlich aus dem unteren Teil der ersten Destillationskolonne abgezogen wird und das durch

25

20

30

wobei R¹ und Ar¹ wie oben definiert sind, dargestellte Alkylarylcarbonat enthält, in die zweite kontinuierliche Mehrstufen-Destillationskolonne umfaßt, um eine Flüssigphasen- und/oder Gas-Flüssigphasen-intermolekulare Umesterungsreaktion innerhalb der gleichen Spezies zwischen Molekülen des Alkylarylcarbonats in Gegenwart eines Katalysators in dieser zweiten Destillationskolonne durchzuführen, wobei ein Reaktionsgemisch mit hohem Siedepunkt, welches ein Diarylcarbonat, dargestellt durch

35

40

wobei Ar¹ wie oben definiert ist, enthält und ein Reaktionsgemisch mit niederem Siedepunkt gebildet wird, welches als Nebenprodukt ein Dialkylcarbonat, dargestellt durch

45

50

enthält, wobei R¹ wie oben definiert ist, wobei das gebildete Reaktionsgemisch mit hohem Siedepunkt kontinuierlich in flüssiger Form aus dem unteren Teil der zweiten kontinuierlichen Mehrstufen-Destillationskolonne abgezogen wird und das Reaktionsgemisch mit niederem Siedepunkt kontinuierlich in Gasform aus einem oberen Teil der zweiten kontinuierlichen Mehrstufen-Destillationskolonne abgezogen wird.

55

7. Verfahren nach Anspruch 6, dadurch gekennzeichnet, daß das Verfahren außerdem die Rückführung des aus dem ob r n Teil der zweiten kontinuierlichen Mehrstufen-Destillationskolonne abg zog nen Reaktionsgemisches mit niederem Si d punkt, welches das durch

R<sup>1</sup>OCOR<sup>1</sup>

5

10

15

20

25

dargestellte Dialkylcarbonat enthält, in die erste kontinuierliche Mehrstufen-Destillationskolonne umfaßt.

- 8. Verfahren nach Anspruch 6 oder 7, dadurch gekennzeichnet, daß der Katalysator ein in der flüssigen Phase löslicher Katalysator ist und in mindestens einer der ersten kontinuierlichen Mehrstufen-Destillationskolonne und der zweiten kontinuierlichen Mehrstufen-Destillationskolonne in gelöstem Zustand in der flüssigen Phase vorliegt und/oder daß der Katalysator ein fester Katalysator ist, der in der flüssigen Phase im wesentlichen unlöslich ist und der in mindestens einer der ersten kontinuierlichen Mehrstufen-Destillationskolonne und der zweiten kontinuierlichen Mehrstufen-Destillationskolonne im in der flüssigen Phase nicht gelösten Zustand vorliegt.
  - 9. Verfahren nach Anspruch 8, dadurch gekennzeichnet, daß der Katalysator ein in der flüssigen Phase löslicher Katalysator ist und in jeder der ersten kontinuierlichen Mehrstufen-Destillationskolonne und der zweiten kontinuierlichen Mehrstufen-Destillationskolonne im in der flüssigen Phase gelösten Zustand vorliegt, wobei die in der ersten und der zweiten Destillationskolonne verwendeten jeweiligen Katalysatoren gleich oder verschieden sind.
  - 10. Verfahren nach Anspruch 6 oder 7, dadurch gekennzeichnet, daß ein Teil oder die Gesamtheit des in der ersten kontinuierlichen Mehrstufen-Destillationskolonne vorliegenden Katalysators im in der flüssigen Phase gelösten Zustand vorliegt und daß bei der Zuführung des Reaktionsgemisches mit hohem Siedepunkt, das in flüssiger Form aus dem unteren Teil der ersten Destillationskolonne abgezogen wird in die zweite kontinuierliche Mehrstufen-Destillationskolonne, das abgezogene Reaktionsgemisch mit hohem Siedepunkt in flüssiger Form in einen ersten Verdampfer eingeführt wird, um eine Trennung des Reaktionsgemisches in eine verdampfte Komponente, wie das durch

30

R<sup>1</sup>OCOAr<sup>1</sup>

35

dargestellte Alkylarylcarbonat enthält, und eine Rückstandsflüssigkeit, die den Katalysator gelöst enthält, zu erreichen, und daß ein Teil oder die Gesamtheit der verdampften Komponente der zweiten kontinuierlichen Mehrstufen-Destillationskolonne zugeführt wird, während ein Teil oder die Gesamtheit der den gelösten Katalysator enthaltenden Rückstandsflüssigkeit in die erste kontinuierliche Mehrstufen-Destillationskolonne zurückgeführt wird.

40

45

11. Verfahren nach Anspruch 6 oder 7, dadurch gekennzeichnet, daß ein Teil oder die Gesamtheit des in der zweiten kontinuierlichen Mehrstufen-Destillationskolonne vorliegenden Katalysators im in der flüssigen Phase gelösten Zustand vorliegt und daß das Verfahren außerdem die Zuführung des in flüssiger Form aus dem unteren Teil der zweiten Destillationskolonne abgezogenen Reaktionsgemisches mit hohem Siedepunkt in einen zweiten Verdampfer umfaßt, um eine Trennung des Reaktionsgemisches in eine verdampfte Komponente, die ein durch

Ar<sup>1</sup>OCOAr<sup>1</sup>

## O

50

55

dargestelltes Diarylcarbonat enthält, und eine Rückstandsflüssigkeit, die den Katalysator gelöst enthält, durchzuführ n, und di Rückführung eines Teils od r der Gesamth it d r den gelöst n Katalysator enthalt nden Rückstandsflüssigk it in die zweit kontinuierlich Mehrstufen-D stillationskolonne umfaßt.

12. Verfahren nach Anspruch 10, dadurch gekennz ichnet, daß in T il oder di Gesamtheit des in der zweiten kontinuierlichen M hrstufen-Destillationskolonne vorli g nden Katalysators im in der flüssigen Pha-

s gelöst n Zustand v rli gt und daß das V rfahren außerd m das Zuführ n d s in flüssig r Form aus dem unter n Teil der zweiten Destillationskolonne abgezogen n R aktionsgemisch s mit hohem Si depunkt in ein n zweiten Verdampfer, um in Trennung des Reaktionsgemisches in eine verdampfte Komponente, die ein durch

10

5

dargestelltes Diarylcarbonat enthält, und eine Rückstandsflüssigkeit, die den Katalysator gelöst enthält, durchzuführen und die Rückführung eines Teils oder der Gesamtheit der Rückstandsflüssigkeit, die den gelösten Katalysator enthält, in die zweite kontinuierliche Mehrstufen-Destillationskolonne umfaßt.

15

13. Verfahren nach Anspruch 1 oder 2, dadurch gekennzeichnet, daß der Katalysator aus der folgenden Gruppe ausgewählt ist: einer Bleiverbindung, einer Verbindung eines Metalls der Kupfergruppe, einem Alkalimetallkomplex, einem Zinkkomplex, einem Cadmiumkomplex, einer Verbindung eines Metalls der Eisengruppe, einem Zirkoniumkomplex, einer Lewis-Säure oder einer eine Lewis-Säure bildenden Verbindung, einer Organozinnverbindung und einem anorganischen Oxid.

20

14. Verfahren nach einem der Ansprüche 3 bis 12, dadurch gekennzeichnet, daß der Katalysator aus folgender Gruppe ausgewählt ist: einer Bleiverbindung, einer Verbindung eines Metalls der Kupfergruppe, einem Alkalimetallkomplex, einem Zinkkomplex, einem Cadmiumkomplex, einer Lewis-Säure oder einer eine Lewis-Säure bildenden Verbindung, einer Organozinnverbindung und einem anorganischen Oxid.

25

15. Verfahren nach Anspruch 1, 2 oder 13, dadurch gekennzeichnet, daß die kontinuierliche Mehrstufen-Destillationskolonne dem Bodenkolonnen-Typ, dem Füllkörperkolonnen-Typ oder dem Mischtyp aus Bodenkolonne und Füllkörperkolonne angehört.

30

16. Verfahren nach einem der Ansprüche 3 bis 14, dadurch gekennzeichnet, daß jeweils die erste kontinuierliche Mehrstufen-Destillationskolonne und die zweite kontinuierliche Mehrstufen-Destillationskolonne unabhängig voneinander dem Bodenkolonnen-Typ, dem Füllkörperkolonnen-Typ oder dem Mischtyp aus einer Bodenkolonne und einer Füllkörperkolonne angehören.

35

# Revendications

40

 Procédé de production d'un carbonate aromatique, qui consiste à transestérifier une matière de départ choisie parmi les dialcoylcarbonates représentés par

45

les alcoylarylcarbonates représentés par

50

et leurs mélanges, avec un réactif choisi parmi les composés aromatiques hydroxy représentés par Ar¹OH , les alcoylaryl- carbonat s représentés par

5

10

et leurs mélanges, chacun de R¹, R² et R³ représentant indépendamment un groupe alcoyle, ayant de 1 à 10 atomes de carbone, un groupe alicyclique ayant de 3 à 10 atomes de carbone ou un groupe aralcoyle ayant de 6 à 10 atomes de carbone, et chacun de Ar¹, Ar² et Ar³ représentant indépendamment un groupe aromatique ayant de 5 à 30 atomes de carbone, pour produire un carbonate aromatique ou un mélange de carbonates aromatiques correspondant à la matière de départ et au réactif et représenté par



15

dans lesquelles R et Ar sont respectivement choisis parmi R¹, R² et R³, et choisis parmi Ar¹, Ar² et Ar³, en correspondance avec la matière de départ et avec le réactif, et pour produire un alcool aliphatique, un dialcoylcarbonate ou leurs mélanges correspondant à la matière de départ et au réactif et représenté par ROH et/ou

ROÇOR,

25

30

35

40

45

20

dans lesquelles R est tel que défini ci-dessus, en tant que sous-produit, caractérisé en ce qu'il consiste à charger en continu la matière de départ et le réactif dans une colonne de distillation continue à étages multiples pour effectuer entre eux une réaction de transestérification en phase liquide et/ou en phase gaz-liquide, en la présence d'un catalyseur dans la colonne de distillation, tout en soutirant en continu un mélange de réaction à point d'ébullition élevé, contenant le carbonate aromatique ou le mélange de carbonates aromatiques produit sous une forme liquide, de la partie inférieure de la colonne de distillation, et en soutirant en continu un mélange de réaction à bas point d'ébullition, contenant le sous-produit sous forme gazeuse, de la partie supérieure de la colonne de distillation par distillation, ce qui permet de produire en continu le carbonate aromatique ou le mélange de carbonates aromatiques.

- 2. Procédé suivant la revendication 1, caractérisé en ce que le catalyseur est un catalyseur qui est soluble dans la phase liquide et qui est présent, à l'état dissous dans la phase liquide, dans la colonne de distillation continue à étages multiples et/ou le catalyseur est un catalyseur solide qui est sensiblement insoluble dans la phase liquide et qui est mis, à l'état non dissous dans la phase liquide, dans la colonne de distillation continue à étages multiples.
- 3. Procédé suivant la revendication 1, caractérisé en ce que la colonne de distillation continue à étages multiples est utilisée comme première colonne de distillation continue à étages multiples et est reliée à une deuxième colonne de distillation continue à étages multiples, et que la matière de départ et le réactif, qui sont chargés en continu à la première colonne de distillation continue à étages multiples, sont respectivement un dialcoylcarbonate représenté par

R<sup>1</sup>ocor<sup>1</sup>

55

50

et un composé aromatique hydroxy représenté par Ar¹OH, le carbonate aromatique ou le mélange de carbonat s aromatiques cont nu dans l mélang réactionnel à haut point d'ébullition produit, qui est soutiré de la parti inféri ur d la pr mière colonne de distillation, st un alcoylarylcarbonate représenté par



dans laquelle R¹ et Ar¹ sont tels que définis ci-dessus, et le sous-produit, contenu dans le mélange réactionnel à bas point d'ébullition produit soutiré en continu de la partie supérieure de la première colonne de distillation, est un alcool aliphatique représenté par R¹OH, et le procédé consiste en outre à charger en continu le mélange réactionnel à point d'ébullition élevé produit et soutiré en continu de la partie inférieure de la première colonne de distillation et contenant l'alcoylaryle carbonate représenté par

dans laquelle R¹ et Ar¹ sont tels que définis ci-dessus, et un alcoylaryle carbonate servant de réactif représenté par

dans laquelle R³ est identique ou différent de R¹, et Ar³ est identique ou différent de Ar¹, sous réserve que R³ et Ar³ ne soient pas respectivement simultanément identiques à R¹ et à Ar¹, dans la deuxième colonne de distillation continue à étages multiples pour effectuer entre eux une réaction de transestérification en phase liquide et/ou en phase gaz-liquide en la présence d'un catalyseur dans la deuxième colonne de distillation, de manière à produire un mélange réactionnel à haut point d'ébullition contenant un diarylcarbonate ou un mélange de diarylcarbonates représentés par

dans lesquelles Ar<sup>1</sup> et Ar<sup>3</sup> sont tels que définis ci-dessus et un mélange réactionnel à bas point d'ébullition contenant comme sous-produit un dialcoylcarbonate représentés par

dans lesquelles R¹ et R³ sont tels que définis ci-dessus, le mélange réactionnel à haut point d'ébullition produit étant soutiré en continu sous une forme liquide de la partie inférieure de la deuxième colonne de distillation, et le mélange réactionnel à bas point d'ébullition étant soutiré en continu sous forme gazeuse de la partie supérieure de la deuxième colonne de distillation par distillation.

4. Procédé suivant la revendication 3 caractérisé en c qu le catalys ur est un catalyseur qui est soluble dans la phas liquide et est prés nt à l'état dissous dans la phase liquid , dans au moins l'une d s première et deuxièm colonnes de distillation continue à étages multipl s t/ou le catalyseur est un catalyseur solid qui st sensiblement insoluble dans la phase liquide et qui st mis, à l'état non dissous dans

la phase liquid, dans au moins l'une d's premièr et deuxième colonnes de distillation continu à étages multiples.

5. Procédé suivant la rev ndication 3 ou 4, caractérisé en ce que R³ est identique à R¹, et Ar³ est différ nt de Ar¹, et le procédé consiste en outre à recycler le mélange réactionnel à bas point d'ébullition soutiré de la partie supérieure de la deuxième colonne de distillation continue à étages multiples et contenant un dialcoyl- carbonate représenté par

R<sup>1</sup>OCOR<sup>3</sup>

à la première colonne de distillation continue à étages multiples.

10

20

25

30

35

40

50

6. Procédé suivant la revendication 1, caractérisé en ce que la colonne de distillation continue à étages multiples est utilisée comme première colonne de distillation continue à étages multiples et est reliée à une deuxième colonne de distillation continue à étages multiples, et que la matière de départ et le réactif qui sont chargés en continu à la première colonne de distillation continue à étages multiples sont respectivement un dialcoylcarbonate représenté par

R<sup>1</sup>OCOR<sup>1</sup>

et un composé aromatique hydroxy représenté par Ar¹OH, le carbonate aromatique ou le mélange de carbonates aromatiques contenu dans le mélange réactionnel à haut point d'ébullition produit et soutiré en continu de la partie inférieure de la première colonne de distillation étant un alcoylarylcarbonate représenté par

R<sup>1</sup>OCOAr<sup>1</sup>

dans laquelle R¹ et Ar¹ sont tels que définis ci-dessus, et le sous-produit, contenu dans le mélange réactionnel produit à bas point d'ébullition soutiré en continu de la partie supérieure de la première colonne de distillation, est un alcool aliphatique représenté par R¹OH, et le procédé consiste en outre à charger en continu le mélange réactionnel à haut point d'ébullition produit et soutiré en continu de la partie inférieure de la première colonne de distillation et contenant l'alcoylarylcarbonate représenté par

R<sup>1</sup>OCOAr<sup>1</sup>,

dans laquelle R¹ et Ar¹ sont tels que définis ci-dessus, dans la deuxième colonne de distillation continue à étages multiples, pour effectuer une réaction de transestérification en phase liquide et/ou en phase gaz-liquide intermoléculaire entre les mêmes espèces, entre des molécules de l'alcoylarylcarbonate en la présence d'un catalyseur dans la deuxième colonne de distillation, de manière à produire un mélange réactionnel à haut point d'ébullition contenant un diarylcarbonate représenté par

Ar<sup>1</sup>ocoar<sup>1</sup>

dans laquelle Ar¹ est tel que défini ci-dessus, tun mélange réactionnel à bas point d'ébullition cont nant un dialcoylcarbonat à titre de sous-produit représenté par

R<sup>1</sup>ocoR<sup>1</sup>,

dans laquelle R¹ est tel que défini ci-dessus, le mélange réactionnel à haut point d'ébullition produit, étant soutiré en continu sous une forme liquide de la partie inférieure de la deuxième colonne de distillation continue à étages multiples, et le mélange réactionnel à bas point d'ébullition étant soutiré en continu sous forme gazeuse de la partie supérieure de la deuxième colonne de distillation continue à étages multiples.

7. Procédé suivant la revendication 6, caractérisé en ce qu'il consiste en outre à recycler le mélange réactionnel à bas point d'ébullition, soutiré de la partie supérieure de la deuxième colonne de distillation continue à étages multiples et contenant le dialcoylcarbonate représenté par

R<sup>1</sup>OCOR<sup>1</sup>,

à la première colonne de distillation continue à étages multiples.

5

10

15

20

25

30

35

40

45

- 8. Procédé suivant la revendication 6 ou 7, caractérisé en ce que le catalyseur est un catalyseur qui est soluble dans la phase liquide et est présent, à l'état dissous dans la phase liquide, dans l'une au moins des première et deuxième colonnes de distillation continue à étages multiples et/ou le catalyseur est un catalyseur solide qui est sensiblement insoluble dans la phase liquide et qui est mis, à l'état non dissous dans la phase liquide, dans l'une au moins des première et deuxième colonnes de distillation continue à étages multiples.
- 9. Procédé suivant la revendication 8, caractérisé en ce que le catalyseur est un catalyseur qui est soluble dans la phase liquide et qui est présent à l'état dissous dans la phase liquide dans chacune des première et deuxième colonnes de distillation continue à étages multiples, les catalyseurs respectifs utilisés dans la première et dans la deuxième colonne de distillation étant les mêmes ou étant différents.
- 10. Procédé suivant la revendication 6 ou 7, caractérisé en ce que tout ou partie du catalyseur utilisé dans la première colonne de distillation continue à étages multiples est présent à l'état dissous dans la phase liquide et, lorsque l'on charge dans la deuxième colonne de distillation continue à étages multiples le mélange réactionnel à haut point d'ébullition soutiré sous forme liquide de la partie inférieure de la première colonne de distillation, on envoie le mélange réactionnel soutiré à haut point d'ébullition sous forme liquide à un premier évaporateur pour effectuer une séparation du mélange réactionnel en un constituant évaporé contenant l'alcoylarylcarbonate représenté par

R<sup>1</sup>OCOAr<sup>1</sup>

- et un liquide résiduel ayant le catalyseur dissous en son sein, et on envoie tout ou partie du constituant évaporé à la deuxième colonne de distillation continue à étages multiples, tout en recyclant tout ou partie du liquide résiduel contenant le catalyseur dissous à la première colonne de distillation continue à étages multiples.
- 11. Procédé suivant la revendication 6 ou 7, caractérisé n c que tout ou parti du catalys ur utilisé dans la deuxième colonne de distillation continu à étages multiples est présent à l'état dissous dans la phase liquide, et le procédé consiste en outre à introduire le mélange réactionnel à haut point d'ébullition, soutiré sous forme liquide de la partie inférieure de la deuxième colonne de distillation, dans un deuxième éva-

porateur pour effectuer un séparation du mélange réactionnel en un constituant évaporé contenant un diarylcarbonate représenté par

ArlocoArl

- 40 et un liquide résiduel ayant le catalyseur dissous en son sein et à recycler tout ou partie du liquide résiduel contenant le catalyseur dissous à la deuxième colonne de distillation continue a étages multiples.
  - 12. Procédé suivant la revendication 10, caracté-risé en ce que tout ou partie du catalyseur utilisé dans la deuxième colonne de distillation continue à étages multiples est présent à l'état dissous dans la phase liquide, et le procédé consiste en outre à introduire le mélange réactionnel à haut point d'ébullition, soutiré sous forme liquide de la partie inférieure de la deuxième colonne de distillation, dans un deuxième évaporateur pour effectuer une séparation du mélange réactionnel en un constituant évaporé contenant un diarylcarbonate représenté par

Ar<sup>1</sup>ocoAr<sup>1</sup>

et en un liquide résiduel

- ayant le catalyseur dissous en son sein, et à recycler tout ou partie du liquide résiduel contenant le catalyseur dissous à la deuxième colonne de distillation continue à étages multiples.
  - 13. Procédé suivant la revendication 1 ou 2, caractérisé en ce que le catalyseur est choisi parmi les composés de plomb, les composés métalliques de la famille du cuivre, les complexes de métal alcalin, les complexes de zinc, les complexes de cadmium, les composés métalliques de la famille du fer, les complexes de zirconium, les acides de Lewis ou les composés formant des acides de Lewis, les composés organo-zinciques et les oxydes minéraux.
  - 14. Procédé suivant l'une des quelconques revendications 3 à 12, caractérisé en ce que le catalyseur est choisi parmi les composés de plomb, les composés métalliques de la famille du cuivre, les complexes de métal alcalin, les complexes de zinc, les complexes de cadmium, les composés métalliques de la famille du fer, les complexes de zirconium, les acides de Lewis ou les composés formant des acides de Lewis, les composés organozinciques et les oxydes minéraux.
- 40 Tocédé suivant la revendication 1, 2 ou 3, caractérisé en ce que la colonne de distillation continue à étages multiples est du type colonne à plateaux, du type colonne garnie ou du type mixte colonne à plateaux et colonne garnie.
- 16. Procédé suivant l'une des quelconques revendications 3 à 14, caractérisé en ce que chacune des première et deuxième colonnes de distillation continue à étages multiples est indépendamment du type colonne à plateaux, du type colonne garnie ou du type mixte colonne à plateaux et colonne garnie.

50

5

15

20

25

30

35

FIG. 1







FIG. 2










FIG.6

